



Construction and Commissioning of Compact-ERL Injector at KEK

Shogo Sakanaka (KEK)
for ERL Development Team in Japan

ERL-2013, 9 -13 September, 2013, at BINP, Novosibirsk, Russia



ERL Development Team in Japan



High Energy Accelerator Research Organization (KEK)

S. Adachi, M. Adachi, M. Akemoto, D. Arakawa, S. Asaoka, K. Enami, K. Endo, S. Fukuda, T. Furuya, K. Haga, K. Hara, K. Harada, T. Honda, Y. Honda, H. Honma, T. Honma, K. Hosoyama, K. Hozumi, A. Ishii, E. Kako, Y. Kamiya, H. Katagiri, H. Kawata, Y. Kobayashi, Y. Kojima, Y. Kondou, T. Kume, T. Matsumoto, H. Matsumura, H. Matsushita, S. Michizono, T. Miura, T. Miyajima, S. Nagahashi, H. Nakai, H. Nakajima, N. Nakamura, K. Nakanishi, K. Nakao, K. Nigorikawa, T. Nogami, S. Noguchi, S. Nozawa, T. Obina, T. Ozaki, F. Qiu, H. Sakai, S. Sakanaka, S. Sasaki, H. Sagehashi, K. Satoh, M. Satoh, T. Shidara, M. Shimada, K. Shinoe, T. Shioya, T. Shishido, M. Tadano, T. Takahashi, R. Takai, T. Takenaka, Y. Tanimoto, M. Tobiyaama, K. Tsuchiya, T. Uchiyama, A. Ueda, K. Umemori, K. Watanabe, M. Yamamoto, Y. Yamamoto, Y. Yano, M. Yoshida



Japan Atomic Energy Agency (JAEA)

R. Hajima, S. Matsuba, R. Nagai, N. Nishimori, M. Sawamura, T. Shizuma



The Graduate University of Advanced Studies (Sokendai)

E. Cenni



Institute for Solid State Physics (ISSP), University of Tokyo

H. Takaki



UVSOR, Institute for Molecular Science

M. Katoh



Hiroshima University

M. Kuriki, H. Iijima



Nagoya University

Y. Takeda, Xiuguang Jin, M. Kuwahara, T. Ujihara, M. Okumi



National Institute of Advanced Industrial Science and Technology (AIST)

D. Yoshitomi, K. Torizuka



JASRI/SPRING-8

H. Hanaki




Yamaguchi University

H. Kurisu

Outline

- I. KEK “PEARL” project and status of Compact ERL
- II. Commissioning of cERL injector
- III. Construction status of return loop
- IV. Conclusion
- V. Acknowledgment

I. KEK "PEARL" Project and Status of Compact ERL




ERL Light Source Project (PEARL) at KEK



Photon Factory ERL
Advanced Research
Laboratory

ERL-based Light Source Project at KEK (2 Stages)

- ① 3-GeV ERL as VUV and X-ray SR source
- ② 6-7 GeV XFEL Oscillator




[1] "Energy Recovery Linac Conceptual Design Report", KEK Report 2012-4 (Oct. 2012);
<http://ccdb5fs.kek.jp/tiff/2012/1224/1224004.pdf>


Tentative Design of 3-GeV ERL

Assumptions:

- Beam energy
 - Full energy: 3 GeV
 - Injection and dump :10 MeV
 - XFEL-O: 6-7 GeV
- Circumference : ~ 1600 m
- Main linac
 - Eight 9-cell cavities in a cryomodule
 - 28 cryomodules (224 cavities)
 - Cavity acc. gradient : 13.4 MV/m
 - Triplet QMs between cryomodules
 - Total length : ~ 470 m
(average acc. gradient : 6.4 MV/m)
- TBA cells for ID's
 - 22 x 6 m short straight sections
 - 6 x 30 m long straight sections
- 300-m long straight section



By N. Nakamura, M. Shimada,
and Y. Kobayashi




Layout at KEK Tsukuba Campus

Purpose of the Compact ERL (cERL) at KEK

- To demonstrate generation, acceleration, and recirculation of low-emittance, high-current beams, which are needed to construct the 3-GeV ERL.
- To demonstrate stable operation of critical components such as the photocathode DC gun and superconducting cavities
- Initial goal: normalized emittance of 1 mm·mrad @7.7pC/bunch (10mA), 35 MeV
- After commissioning, use cERL as laser-Compton X-ray source and high-intensity terahertz source

Design parameters of cERL

Parameter	Goal (future goal in ())
Beam kinetic energy	35 MeV (upgradable to 125 MeV)
Injector kinetic energy	5 MeV (10 MeV)
Average current	10 mA (100 mA)
Normalized emittance @bunch charge	0.3 mm·mrad @7.7 pC 1 mm·mrad @77 pC
Bunch length (rms)	1 - 3 ps < 150 fs (with B.C.)
Accelerating gradient (main linac)	15 MV/m
RF frequency (= bunch repetition frequency)	1.3 GHz




Construction Site@KEK



Commissioning of injector started in April, 2013.



Layout of cERL (plan)



cERL Injector was completed (April, 2013)



500-kV Photocathode DC gun (#1) at JAEA


Nishimori's Talk

Ideas


- Segmented insulator for protecting ceramics
- Measures for avoiding big sparks
 - Improved pumping speed
 - Increasing anode-cathode gap: 100 → 160 mm (E : 6.7 → 5.8 MV/m)

Goals

High voltage	500 kV
Electric field on cathode	> 5MV/m
Beam current	100 mA
Normalized emittance	0.1-1 mm·mrad



Successful production of 500-keV, 1.8 mA beam



N. Nishimori et al., Appl. Phys. Lett. 102, 234103 (2013).




Summary of performance

- Successful production of 500-keV, 1.8-mA beams at JAEA
- Maximum electric field on cathode: 5.8 MV/m (@500 kV)
- Normalized emittance: 0.07 mm·mrad @10fC (at cERL, $V=390$ kV)
- Long term operation (~ 260 hours) at $V=390$ kV at cERL


Status of 500-kV Photocathode DC Gun (#2)

Yamamoto's Talk

High voltage power supply was tested up to 580 kV.



Very-low outgassing rate in overall gun-system



High pumping speed of bakable cryopump under extremely-high vacuum

Gun-Drive Laser System


By Yosuke Honda

System


- 1.3GHz Nd:YVO₄ oscillator ($\lambda=1064$ nm)
- Yb photonic-fiber amplifiers (two stages)
- Second-harmonic generation ($\lambda=532$ nm)
- Temporal shaping with birefringent crystal
- Gate system for CW/macropulse operations

Specifications

- Maximum beam current: 10 mA (CW)
- Laser power: 2.3 W@532 nm (if Q.E.=1%)
(P=70 W@1064 nm has been demonstrated)




Gun-Drive Laser System



Laser profile at virtual cathode CCD camera.



Drive-Laser System





Laser transport line


High-Power Test of Injector Cryomodule

By E. Kako et al.

Processing of Cavity -2 : (2013, Feb. 7-8, 13)



HOM coupler suitable for CW operation





Ideas and specifications

- Improved HOM couplers/feedthroughs for CW operation
- Beam current: 10 mA (100 mA in future)
- $\Delta T=5$ MeV with three two-cell cavities
- Two input couplers/cavity
- Five HOM couplers/cavity

Summary of performance

- Demonstrated $E_{acc} = 15$ MV/m in pulsed operation (duty 10%)
- Demonstrated $E_{acc} = 8$ MV/m in CW operation
- Stable long-term operation (~ 260 hours) at $E_{acc}=7.1$ MV/m. Almost no trips during cERL operations.
- Relatively-large dynamic losses (low- Q_0) due to heating-up of HOM feedthroughs. We plan to improve the feedthroughs and cooling.

Qo measurement of Cavity -2




High-power Test of Main-Linac Cryomodule

By T. Furuya et al.

Hara's poster (PS15)


Specifications

RF frequency: 1.3 GHz
 Input power : 20 kW CW (SW)
 E_{acc} : 15 - 20 MV/m
 Unloaded-Q: $Q_0 > 1 \times 10^{10}$
 Beam current : max 100 mA
 (HOM-damped cavity)




Summary of performance

- $V_c=16$ MV was achieved for both cavities.
- $V_c=13.5-14$ MV could be kept for more than 1 hour
- Onset of radiation due to field emission: 8-10 MV/cavity (not very good)
- To increase the onset of field emission, we plan to refine module-assembly technique.



Measured Q_0 vs V_c
 $(V_c = 1.038 \times E_{acc})$



Onset of radiation' (field-emission)


II. Commissioning of cERL Injector



cERL Injector (upstream part)




Photocathode DC gun (#1)



Injector Beamline and Diagnostics


By T. Miyajima
and Y. Honda



Buncher cavity




Screen monitors
(MS1 - MS7)



Slit scanner for
emittance measurement




2.6-GHz deflecting cavity for
bunch-length measurement



Optics Design of cERL Injector

By T. Miyajima

Plane layout of cERL injector




Simulations using
GPT code




- Parameters for simulations are given in the next slide.
- Note that similar parameters to those under beam operations were chosen.
- These parameters might not be optimum for emittance minimization.

Low charge: ~ 10 fC/bunch



High charge: 7.7 pC/bunch



Typical Parameters of cERL Injector

By T. Miyajima
and Y. Honda

	Simulation (low charge)	Simulation ($q_b=7.7$ pC)	Operation (low charge)	Operation ($q_b=7.7$ pC)
Charge/bunch	~ 10 fC	7.7 pC	~10 fC	7.7 pC
Gun DC voltage	390 kV	390 kV	390 kV	390 kV
Spot diameter of laser	1.1 mm	1.1 mm	1.2 mm	1.2 mm
Laser pulse width	3 ps rms (Gaussian)	16 ps FWHM (flat)	3.3 ps rms (Gaussian)	15.7 ps FWHM (semi-flat)
Magnetic fields of solenoids #1, #2	(0.020, 0.024) T	(0.029, 0.018) T	(0.0248, 0.0103) T	(0.0286, 0.0172) T
Voltage and phase of buncher cavity (0 degree: on-crest)	0 kV	50 kV, -90 deg.	0 kV or 40 kV, -90 deg.	50 kV, -90 deg.
E_{acc} of three injector cavities	(6.1, 6.1, 6.1) MV/m	(7, 7, 7) MV/m	(6.2, 6.7, 6.2) MV/m	(6.2, 6.7, 6.2) MV/m
Phase of three injector cavities (0 degree: on-crest)	(0, 0, 0) degree	(0, 0, 0) degree	(0, 0, 0) degree	(0, 0, 0) degree
Beam kinetic energy after acceleration	5 MeV	5.7 MeV	Typ. 5.5 MeV	Typ. 5.5 MeV

Parameters similar to those under beam operations were chosen (not optimum for emittance minimization).

Typical parameters of
macropulse-beam operation:

Macropulse beams were used for
destructive beam measurements.


Repetition frequency of bunches	1.3 GHz
Charge/bunch	10 fC - 7.7 pC
Repetition rate of macropulses	5 Hz (typ.)
Width of macropulse	1 μ s (typ.) or 1.6 ms (for high average current)
Rise/fall times of macropulse	~10 ns

Successful Acceleration of Beams to 5.6 MeV (22-26 April, 2013)


Gun voltage: 390 kV
 Injector cavities: $E_{acc}=7.1$ MV/m
 Macro-pulse beams for diagnostics
 Maximum beam current achieved: 200 nA

Bunch repetition rate	1.3 GHz
Micro-pulse widths	1 μ s or 1.6 ms (for high current)
Repetition of macropulses	5 Hz
Charge/bunch	Typically 20 fC


MS2
T=390 keV




MS3
T~5 MeV




MS4
Accelerated beam



MS6
(before BM)



MS7 (after BM)
 $\eta=0.825$ m



Beam-current signal at a faraday cup




Photo-cathode DC gun

Injector cryomodule

Beam
→

Injector beam dump


Emittances of Beams from the Gun (T=390 keV, very-low charge)

Honda's Poster
(PS03)




Gun voltage: 390 kV, Charge/bunch ~10 fC

Solenoid-scan method

$$k = \left(\frac{eB_0}{2mc\beta\gamma} \right)^2 \ell_{sol}$$




Example of solenoid scan (scan SL2, monitor MS3)



Set of measurements

Normalized emittance:
 $\epsilon_n \approx 0.07 \mu\text{m}\cdot\text{rad}$
(at T =390 keV)


Typical beamprofile at screen monitor MS1




Beam Emittances of Accelerated Beams (T=5.6 MeV, low bunch charges)

Honda's Poster
(PS03)


Slit-scan method



Charge: 0.02 pC/bunch
(buncher off)




Horizontal phase-space distribution



Vertical phase-space

Setup of measurement




Slit width:
0.1 mm


Measurement conditions:

Measured on 21-June-2013
After fine RF-phase tuning
Buncher: OFF or ON ($V_c=40$ kV)
Laser: short-pulse (~ 3 ps rms)
Bunch charges: 0.02, 0.77 pC

Charge: 0.77 pC/bunch
(buncher off)




Horizontal phase-space



Vertical phase-space

Normalized rms emittance ($\mu\text{m}\cdot\text{rad}$)



Charge/bunch (pC)

Results:


$\epsilon_n \approx 0.17 \mu\text{m}\cdot\text{rad}$ at 0.02 pC
 $\epsilon_n \approx 0.3 \mu\text{m}\cdot\text{rad}$ at 0.77 pC

Emittances might be smaller due to the limitation of the measurement


Beam Emittances at High Charges (tentative results) (T=5.6 MeV, up to 7.7 pC/bunch)

Honda's Poster
(PS03)

Beam profiles at
screen monitor MS6



7.7 pC/bunch



1.5 pC/bunch


Conditions of measurements

Meas. Date	Bunch charge (pC)	Width of laser pulse	Buncher Vc (kV)	Solenoids (SL1, SL2)
21-June-2013	0.02, 0.77	3 ps (rms, Gaussian)	40	7.8/8.7, 3.0
26-June-2013	3.1, 7.7	3 ps (rms, Gaussian)	50	8.3, 4.99
28-June-2013	1.5, 7.7	16 ps (FWHM, semi-flat)	50	8.3, 4.99


Bunch lengths

3-ps laser

16 ps semi-flat



Summary of measurements



Tentative result:

$$\varepsilon_n \approx 0.8 \mu\text{m}\cdot\text{rad} \text{ at } 7.7 \text{ pC}$$

(not fully optimized yet)

Comments


- Axially asymmetric beam profile. Not yet understood. (Due to beam offset in SC/buncher cavities?)
- Tentatively, beam emittances depended only weakly on laser-pulse widths.
- Gun voltage is lower than the design value ($V_{\text{gun}} = 390 \text{ kV}$)

Machine parameters have not been optimized yet !


Bunch-Length Measurements

Honda's Poster (PS03)


Measurement method




Deflecting cavity ($f = 2.6$ GHz)



Resolution of the measurement:
~0.7 ps



Bunch length vs. bunch charge (buncher $V_c=50$ kV)



Laser: 3 ps rms
Buncher 50 kV

Laser: 16 ps semi-flat
Buncher OFF


Laser: 16 ps semi-flat
Buncher 50 kV

* Machine parameters were probably not optimum under space-charge effects


Spread and Stability of Beam Momentum

By Y. Honda
and T. Miura

Setup of measurement




Energy Spread vs. bunch charge (buncher Vc=50 kV)



Stability of beam momentum

Miura's talk


Before optimization



FB1: high gain
FB2: low gain

FB1: high gain
FB2: high gain

After optimization



FB1: high gain
FB2: low gain

FB1: high gain
FB2: high gain

Momentum jitter :
 $(\Delta p/p)_{\text{rms}} \approx 6 \times 10^{-5}$

What was optimized?

- Parameters of digital RF-feedback system
- On-crest phases of three injector cavities were precisely adjusted

Typical Operation Status (23-May-2013)

DesktopState4.opi
CSS

2013/05/23 13:36:27
Message
Radiation Check

電荷制限器ステータス

電流値 **0.286 μ A** (Beam current)

17.6 %

加速電圧 **4.857 MV**

機器運転状態

電子銃

加速用高周波

Laser Status

Gun-GV SC-1stGV

Final Shutter

LaserRoom Shutter

Fast Mec Shutter

Fast Elec Shutter

Laser Oscillator

Laser Final Shutter

Yellow Monitor

Radiation Monitor

LLRF Status

BUNCHER (IOT)	Inj1 (30kW KLYSTRON)	Inj2/Inj3 (300kW KLYSTRON)
HV OFF	HV ON	HV ON
Interlock OFF	OK	OK
RF ON/OFF OFF	ON	ON
Power 0.000 [kW]	2.773 [kW]	17.132 [kW]

cEERL Vacuum

Pressure (Pa)

Gun

Injector SCC

Pressure in the Gun: $< 2 \times 10^{-9}$ Pa

Eacc, RF power and Phase for Injector SC cavities

	Eacc(Pt)	Eacc(Pin)	Pin	Pt	Phase
CAV#1	7,113 MV/m	7,474 MV/m	2,960 kW	229,000 mW	-0,917 V
CAV#2	7,248 MV/m	8,989 MV/m	8,870 kW	306,500 mW	1,538 V
CAV#3	6,819 MV/m	7,858 MV/m	8,140 kW	274,500 mW	0,620 V

Accelerating Gradients of Injector Cavities (MV/m)

Beam Current (μ A)

550kV Electron-Gun Power Supply

- 高圧ON
- 外部1+1k (PPS) OK
- 外部1+1k (MMS) OK
- 運転電圧1+1k OK
- 運転電圧2+1k OK
- 1+1k OK
- 主電源ON
- リモート
- 1p1正常
- Vp1正常
- FAN正常
- IGBT温度正常

Gun Voltage (kV)

Operation Statistics of cERL-Injector (April - June, 2013)

Month	Machine Operation Time* (hours)	Beam ON Time (hours)	Operation Time of Helium Refrigerator (hours)
April	92	24	185
May	111	70	291
June	157	106	315
Total	361	202	792

* Including conditioning

Present Performance of cERL Injector (at the end of June, 2013)

Parameter	Achieved	Comment and Outlook
Kinetic beam energy T	5.6 MeV (typ.), 5.9 MeV (max.)	$T \leq 6$ MeV is allowed at present.
Average Beam current I_0	300 nA (max.)	$I_0 \leq 1$ μ A is allowed at present. Beam current will be increased step by step.
Gun High Voltage V_{gun}	390 kV (typ.)	Very stable for more than 200 hours. Higher voltage is expected by polishing insulating ceramics.
Accelerating gradient of injector cavities E_{acc}	7 MV/m (typ.)	CW operation. Very stable for more than 200 hours.
Normalized beam emittance (T=390 keV, low charge)	≈ 0.07 $\mu\text{m}\cdot\text{rad}$ (@~10 fC/bunch)	
Normalized beam emittance (T \approx 5.6 MeV, low charge)	≈ 0.17 $\mu\text{m}\cdot\text{rad}$ (@0.02 pC/bunch)	Close to the limitation of present instrumentation. Emittance might be smaller.
Normalized beam emittance (T \approx 5.6 MeV, high charge)	≈ 0.8 $\mu\text{m}\cdot\text{rad}$ (@7.7 pC/bunch)	Further improvement is expected by optimizing machine parameters and by higher gun voltage.
Momentum jitter $(\Delta p/p)_{\text{rms}}$	6×10^{-5}	On-crest acceleration. With high rf-feedback gain.
Bunch length and energy spread	See graphs in these slides. (depend on bunch charges)	Parameters have not been optimized yet under space-charge effect.

III. Construction Status of Return Loop



Return loop is under construction (July - November, 2013)

Schedule

- Jul. - Nov., 2013 : Construction of return loop
- Nov. (2nd half) : Conditioning of SC cavities
- Dec. 2013 : Commissioning of cERL

Linear optics of cERL

Shimada's Talk



1st arc



South straight section




Alignment of magnets

Future Schedule

Dec. 2013 - Mar. 2014	Initial commissioning of cERL (beam current: 10 μ A max.)
Apr. - Dec. 2014	Operation and study of cERL Construction of Laser-Compton Scattering (LCS) beamline
Jan.(?) - Mar., 2015	Commissioning of LCS beamline (by JAEA) Increasing beam current
Apr. 2015 -	Machine study Operation for LCS and THz beamlines → Nozawa's Poster (PS01)

Laser-Compton Scattering
X(γ)-ray Beamline
(by JAEA)



IV. Conclusion

Construction

- 6-MeV cERL injector was completed and commissioned in April 2013.
- Return loop of cERL is under construction (Jul. - Nov. 2013).
- Commissioning of entire cERL is scheduled in Dec. 2013.

Commissioning of injector

- We operated cERL injector for about three months (22 Apr. - 28 Jun., 2013)
- Both photocathode DC gun ($V=390$ kV) and injector SC cavities ($E_{acc}=7$ MV/m) could be operated **very stably**. We observed almost no trips due to these components.
- We observed very-low normalized emittances ($\approx 0.1-0.2$ $\mu\text{m}\cdot\text{rad}$) at low charges (~ 10 fC/bunch) at $T=390$ keV and $T=5.6$ MeV.
- At high charges (~ 7.7 pC/bunch), we are **on the way to optimize** the parameters. At the moment, we observed normalized emittances of about **0.8 $\mu\text{m}\cdot\text{rad}$** .
- We also observed **axially asymmetric profiles** of beams at high charges, which should be understood. (Maybe, hybrid effect of space charge and beam offset in cavities?)

V. Acknowledgment

Collaboration and Discussions


We are grateful to the [Cornell University](#), [Argonne National Laboratory](#), [Jefferson Lab.](#), [TRIUMF](#), [HZDR](#), [HZB](#), [ASTeC](#), and the other institutes, for useful discussions, advices, or collaboration.

Special Thank

We sincerely express our thank to [Dr. Gennady N. Kulipanov](#), the chairman of this workshop, for his series of seminars and fruitful discussions during his stay in KEK (Sep. - Oct., 2001). His deep insight stimulated us interests in future light sources based on recirculating linacs and ERLs.



Dr. Kulipanov



One of the OHP sheets of his seminar in 2001.

Let's collaborate together !



Picture taken on March 27, 2013