



IPAC13 in Shanghai
13, May, 2013

ADS Program and Key Technology R&D in China

Wenlong Zhan CAS & ADS Group(IMP, IHEP, IPP)




OUTLINE

I. Introduction of ADS

- Motivation
- ADS Roadmap in China

II. Progress of ADS in China


- Overview of C-ADS
- Accelerator System
- Spallation Target
- New Site, New Research Center






Motivation

- Accelerator Driven System was proposed for nuclear waste transmutation, accelerator driven thorium reactor (ADTR)...., since early 1990's
- ADS produce hard, intense spallation neutron by accelerating high power proton on target for driving subcritical core
- ADS consists of high power proton accelerator & spallation target, subcritical core




ADS and FR in Advanced Nuclear Fuel Cycles — A Comparative Study, NEA/OECD, 2002





Nuclear Fuel Cycle (IAEA-TECDOC-1613)


Open Cycle





Nuclear Fuel Cycle (IAEA-TECDOC-1613)


Close Cycle






Nuclear Fuel Cycle (IAEA-TECDOC-1613)

ADS+Close Cycle



Total radiotoxicity of spent fuel relative to the radiotoxicity of natural uranium ore.

- **Used fuel** → Open Cycle (~300,000y)
- **Pu & U removed** → Close Cycle (~5,000y)
- **Pu, U, & MA removed** → ADS + Close Cycle (~300y)







Advanced Nuclear Fuel Cycles

● *ADS and FR in Advanced Nuclear Fuel Cycles — A Comparative Study*, NEA/OECD, 2002

- ADS is better at burning waste than Fast Reactors
- ADS employs a fast neutron spectrum and solid, fertile-free fuel with the primary mission of transmuting transuranics or MA
- ADS could support more PWR waste transmutation
-






ADS Activities (except US & CN)

项目		加速器功率 (MW)	K_{eff}	堆功率 (MW)	谱通量 ($\text{n}/\text{cm}^2/\text{s}$)	靶	燃料
日本2004 JAERI-ADS		27 (1.5GeV/18mA)	0.97	800	快	铅铋	MA/Pu/ZrN
韩国 HYPER		15 (1GeV/10~16mA)	0.98	1000	快	铅铋	MA/Pu
欧 盟	意/法 XT-ADS-A/B	3.6 (600MeV/3~6mA)	0.95~0.97	80	快 10^{15}	铅铋/ 钢	U/Pu/MOX
	比利时 XT-ADS-C	1.75 (350MeV/5mA)	0.95	50	快 3×10^{15}	铅铋 (无窗)	U/Pu/MOX
	EFIT	16 (800MeV/20mA)	~0.97	数百	快 $\sim 10^{15}$	铅 (无窗)	MA
俄 罗 斯	INR	0.15 (500MeV/10mA)	0.95~0.97	5	快	钨	MA/MOX
	NWB	3 (380MeV/10mA)	0.95~0.98	100	快 $10^{14\sim 15}$	铅铋	UO ₂ /UN U/MA/Zr
	CSMSR	10 (1GeV/10mA)	0.95	800 级联方案	中间 5×10^{15}	铅铋	Np/Pu/MA 熔盐


- ADS demo projects require: ~1GeV&10mA accelerator,
and 10's MW Spallation Target





ADS Technology Readiness (ADS White Paper, DOE, 09/2010)

		Transmutation Demonstration	Industrial-Scale Transmutation	Power Generation
Front-End System	Performance			
	Reliability			
Accelerating System	RF Structure Development and Performance			
	Linac Cost Optimization			
	Reliability			
RF Plant	Performance			
	Cost Optimization			
	Reliability			
Beam Delivery	Performance			
Target Systems	Performance			
	Reliability			
Instrumentation and Control	Performance			
Beam Dynamics	Emittance/halo growth/beamloss			
	Lattice design			
Reliability	Rapid SCL Fault Recovery			
	System Reliability Engineering Analysis			






Nuclear Power Development in China

- **To May 2013 (www.world-nuclear.org/info/...)**

- Operating 17 set reactors, 13.955GW_e ; (6th in world)
- Constructing 28 set reactors, 30.550GW_e ; (1st in world)
- Planned 49 set reactors, 56.020GW_e ; (1st in world)


- **According to some information: (slower after 2011.3)**

- **2020**: $\sim 70\text{GW}_e$ NPP in operation and 30GW_e NPP under construction; $>5\%$ of NP to total installed power capacity
- **2030**: $\sim 10\%$ of NP to total installed power capacity
- **2050**: $>400\text{GW}_e$ NPP $\rightarrow$ **almost same as the scale of the total in the world today's!**





Special Program of NE in CAS (Fund 9/2011)






ADS Roadmap in China



ADS Roadmap in CAS






OUTLINE

I. Introduction of ADS

- Motivation
- ADS Roadmap in China


II. Progress of ADS in China

- Configuration of C-ADS
- Accelerator System
- Spallation Target
- New Site, New Research Center






Configuration of C-ADS






Accelerator System: ECRIS + LEBT






ECRIS+LEBT is commissioning at IMP




The first ECR Proton Ion Source is commissioning at IMP. 25 mA Proton with 35 keV has been extracted.

Stability still need to be improved in long time.






Measurements at the end of LEBT



$V_b = -2\text{kv}$, $G_1 = 230\text{A}$, $G_2 = 261\text{A}$, $S_1 = S_2 = S_3 = S_4 = 0$, $FC02 = 3\text{ mA}$,
 $HV = 35\text{kv}@6\text{mA}$






Accelerator System: Two options of 10-MeV Injectors



Injector I at IHEP, Beijing

Base on 325 MHz and Superconducting Spoke cavity



Injector II at IMP, Lanzhou

Base on 162.5 MHz and Superconducting HWR cavity







Accelerator System: RFQ for Injector I



Parameters	Value
Frequency (MHz)	325
Injection energy (keV)	35
Output energy (MeV)	3.2128
Pulsed beam current (mA)	15
Beam duty factor	100%
Inter-vane voltage V (kV)	55
Beam transmission	98.7%
Average bore radius r_0 (mm)	2.775
Vane tip curvature (mm)	2.775
Maximum surface field (MV/m)	28.88 (1.62Kilp.)
Cavity power dissipation (kW)	272.94
Max. copper power/Area (W/cm ²)	3.77
In norm. rms e (x,y,z) (π mm.mrad)	0.2/0.2/0
Out norm. rms e (x/y/z) (π mm.mrad/MeV-deg)	0.2/0.2/0.0612
Vane length (cm)	467.75
Accelerator length (cm)	469.95

The beam transmission is about 98.7%






Progress of RFQ for Injector I (325MHz)



**Cold test of all modules has been done.
Commissioning is expected on Fall.**






Spoke012 for Injector I



Parameters	Unit	
Freq.	MHz	325
Beta		0.12
Epeak/Eacc		4.3
Bpeak/Eacc	mT/(MV/m)	6.5
Uacc=0.78MV	MV/m	30.1
R/Q	Ω	161




$E_{acc} 8.1 \text{ MV/m} @ Q_0 1.5 \times 10^8$




Accelerator System: RFQ for Injector II

Parameter	Value
Ion species	Proton
frequency [MHz]	162.5
Inter-vane voltage V (kV)	65
Average bore radius r_0 (cm)	0.5731
Vane tip curvature (cm)	0.4298
ρ / r_0	0.75
Vane length / Total length (cm)	419.2 / 420.8
$m_{\max}$	2.38
Number of cells	192 (including 2 T cell)
Maximum surface field (MV/m)	15.7791
Synchronous phase	From -90° to -22.7°
$a_{\min}$ (cm)	0.3158
Transverse acceptance (RMS, x/y, $\pi\text{mm.mrad}$)	0.3/0.3
Input norm. RMS emittance (x/y, $\pi\text{mm.mrad}$)	0.3/0.3
Output norm. RMS emittance (x/y/z, $\pi\text{mm.mrad}$, keV.ns)	0.31/0.31/0.92
Overall beam transmission @ 0 / 15 mA	99.7% / 99.6%




The Radio Frequency Quadrupole

(RFQ) is 4200mm long made from four modules of equal length that bolt together







Progress of RFQ for Injector II (162.5MHz)




Half module



Single wane



Test module is ready for high power testing





HWR010 for Injector II



Freq. (MHz)	162.5
--------------------	--------------

β_{opt}	0.10
---------------------------------	-------------

E_{pk}/E_{acc}	5.34
------------------------------------	-------------


B_{pk}/E_{acc}	10.92
------------------------------------	--------------

Q_0 (@4.5K)	4.1E8
---------------------------------	--------------

U_{acc} (MV)	0.78
----------------------------------	-------------

P_{diss} (W)	10
----------------------------------	-----------


IMP-HWR010-S-002 and 005 Q_0 vs. E_{acc} VTA Results



E_{acc} 8.3MV/m @ Q_0 4.1 $\times$ 10⁸




Progress of Spoke021 for Main Linac



Para.	
$E_p/E_{acc} /(\text{void})$	3.88
$H_p/E_{acc} /mT/(MV/m)$	8.13
β_{opt}	0.246
$r/Q /\Omega$	206
G /Ω	87
$R_{BCS} /n\Omega$	0.68
$Q0@R_{res}=5n\Omega$	1.38E10
$Q_{e,opt}$	7.28E5


Rolling the cylinder
Pulling the port blend

Forming the end plate
& nose-cone




Nb SST brazed joint

Squeezing the spoke pole






Progress of Cavity for Main Linac



	Center cell	End cell
L (cm)	9.461	9.461
E_p/E_{acc}	2.12	
$H_p/E_{acc} \text{ mT}/(\text{MV/m})$	4.05	
$r/Q [\Omega]$	514.6	
G $[\Omega]$	235.5	
k [%]	0.9%	
Field flatness [%]	>98	



Beta=0.85 Freq.=650 MHz





RF Couplers Development




325MHz, Spoke
CW, 10kW
Tested



325 MHz, RFQ
CW, 100 kW
Tested



162.5MHz, HWR
CW, 20kW
Tested






Solid State Amplifiers

Testing Item	Requirements
frequency	162.5 MHz $\pm$ 2 MHz
Freq. stability	$< \pm 1 \times 10^{-8}$ /day
RF standard	0dBm $\sim$ 10dBm continuous tuning
Output Power	≥ 20 kW (CW, Pulse) full reflection
Duty factor	1% $\sim$ 100% tuning
Harmonic	≤ -30 dBc
Harmonic of PS	≤ -50 dBc
Random Harmonic	≤ -60 dBc
Amplitude stability	$\leq \pm 1 \times 10^{-2}$ /24 hours
Phase stability	$\leq \pm 5^\circ$ /24hours, open loop
Output interface	50 Ω coaxial, 4-1/2




The solid state amplifiers of 162.5 MHz at 20 kW and 325 MHz at 10 kW were tested. All specifications are reached.






Cryomodule




Cool down
Operation
Gas return



Valve Box




Test Cryomodule for In







Horizontal Test Stand for Spoke




2K valve box



2K shielding








Cryomodule






Cryomodule for Spoke012




5704 mm, 6 spokes, 6 couplers, 5 solenoids, 5 BPMs, 2 valves inside






Progress of BPM Diagnostics



BPM Manufacturing




BPM electronics measurement



BPM beam measurement in IHEP




BPM's installation in MEBT of Proton LINAC in the IHEP.




Beam energy	3.5MeV
β	0.086
Bunch frequency	352.2 MHz
Average current	18 mA

Movable test bench



移动测试平台底座完成验收
2012-12-10




2012-12-10




Test of Single Wire Scanner

O 7+, 62.5 keV/u





Halo signal




Scan signal

Beam width 10 mm






• Spallation Targets





Spallation Target —

- Two physical designs of LBE targets under testing
- New type solid target under designing

LBE target with window



Windowless LBE target




Forced flow liquid LBE loop
Design and simulation (up) and test set-ups (down)





Principle of Granular Flow Spallation Target

Granular Flow by Gravity



- Granular flow operates similar as sand clock and Heat is treated off line





Design Granular Flow Spallation target


Parameters

Granular material	Tungsten/Tungsten alloy
Structure material	TZM/SiC
Granular size	$10 \pm 5\text{mm}$
Inlet temperature of granular	250 C
Proton beam	1GeV@10mA=10MW
Intensity of beam	$>100 \mu\text{A}/\text{cm}^2$
Diameter of beam spot	10cm

Average temperature increase	Average velocity
400	$\sim 0.8\text{m/s}$
500	$\sim 0.5\text{m/s}$
600	$\sim 0.35\text{m/s}$
800	$\sim 0.25\text{m/s}$




Mass parallel Simulation:
 Contact mechanism + MD + MC transport
 K20GPU 2500ALU * 32
 Number of Ball: 0.5 M






Granular Flow Spallation target: 10's MW







New Site, New Research Center






New Site, New Research Center






Heavy Ion Accelerator Facility (HIAF)

- ◆ (ABR+CBR+ICR): high quality & intensity pulsed RIBs, β & neutron beam $\rightarrow$ high accuracy RIA, astrophysics, application...
- ◆ (ABR+CBR+ICR): high power compressed U beam $\rightarrow$ HED...
- ◆ (ABR+CBR+ICR+ER): polarized e & p beams $\rightarrow$ EIC;
U+U, RIB+RIB... $\rightarrow$ Merging Experiments...






Future Integrate Development





Summary

- **ADS physical, most of technical design and prototype fabrication progress in schedule**
- **Accelerator System (two options in low energy)**
 - ▶ 2.45 MHz ECRIS under testing, 14 MHz ECRIS is optimizing
 - ▶ 162.5 MHz RFQ, HWR & 325 MHz RFQ, Spoke in low energy injectors are fabricating & Testing
- **Spallation Target (two options)**
 - ▶ LBE target designed and constructing
 - ▶ New type of granular flow target was designed and is starting demo construction
- **New site, New institute are fixing soon (slower than schedule)**





Welcome to Collaboration !

THANKS FOR ATTENTION

