

# **Argonne Wakefield Accelerator (AWA): a Facility for the Development of High Gradient Accelerating Structures and Wakefield Measurements**

**Manoel Conde, S. Antipov, D.S. Doran, W. Gai, C. Jing, R. Konecny,  
W. Liu, J.G. Power, E. Wisniewski, Z. Yusof**

**Argonne National Laboratory  
Euclid Techlabs LLC  
Illinois Institute of Technology**

# Research at the AWA Facility


Developing accelerator technology for future HEP machines and other applications.

Desirable characteristics:

- High gradient acceleration (compact)
- Relatively low cost
- Modular (stages)
- Works for electrons and positrons
- Macroscopic beam apertures
- Microwave range of frequencies
- Explores the use of advanced materials




# Wakefields in Dielectric Structures (a short Gaussian beam)



$$W_z(z) \approx \frac{Q}{a^2} \exp\left[-2\left(\frac{\pi \sigma_z}{\lambda_n}\right)^2\right] \cos(kz)$$
$$\sigma_r = \left(\frac{\epsilon_N}{\gamma} \beta\right)^{1/2}$$

## AWA approach:

- High charge drive bunches
- High gradient
- Short RF pulses
- Macroscopic beam apertures
- Microwave frequencies (8 – 26 GHz)



# Reasons for Recent AWA Upgrades

## Have two beam accelerator capability:

Have two parallel beamlines, allowing drive bunches to excite wakefields and accelerate witness bunch.

## Use the demonstrated high gradients to accelerate beam:

The high quality drive beam has excited high gradient accelerating fields (100 MV/m) in dielectric loaded structures. Now these high gradients will be used to accelerate a witness bunch.

## Have higher drive beam energy for high gradient and sustained acceleration:

- Propagation of drive beam through smaller diameter structures, resulting in even higher accelerating gradients.
- More energy available in drive bunches, allowing extraction of higher energy RF pulses.
- Construction of longer structures will demonstrate higher energy gain.


## Have beamline switchyard for added flexibility:

Beamline switchyard will greatly facilitate the implementation of distinct experimental setups: collinear wakefield acceleration, two-beam-acceleration, phase space manipulation and, further into the future, staging.



# AWA Facility

75 MeV drive beam:  
RF gun with Cs<sub>2</sub>Te photocathode  
& six linac tanks




15 MeV witness beam:  
RF gun with Mg photocathode  
& one linac tank

Beamline switchyard  
(under construction)



# New RF Gun with Cesium Telluride Photocathode



## New RF gun installed in AWA bunker:


- 1 ½ cell, L band (1.3 GHz)
- 12 MW, 80 MV/m on cathode
- RF conditioned to 15 MW with Cu photocathode
- Generated beam (single bunches) from Cu and  $\text{Cs}_2\text{Te}$  cathodes



## Cesium Telluride preparation chamber:

- necessary QE  $\sim 1\%$
- routinely achieving QE  $> 10\%$



# New Linac Tanks



- Turnkey fabrication, directly from design to finished cavity
- Designed by ANL/SLAC
- Fabrication by local vendor (Hi Tech)
- Tuned and balanced at Argonne
- Adopted by LBL for the NGLS APEX test beam


- 7 cell  $\pi$  mode, L band (1.3 GHz)
- 10 MW, 11.2 MeV energy gain
- $Q = 26687$   
Shunt = 20.6 Mohm/m  
 $R/Q = 773.4$

Gun and first linac tank




Gun and six linac tanks

# Additional 80 MW of RF Power (three klystrons)



Two new Thales TV 2022X


- L band (1.3 GHz)
- 10 μs, 25 MW



30 MW Litton klystron on loan  
from LANL (thanks to B. Carlsten  
and S. Russell)



# Overview of AWA Beamlines





# Objectives to be Achieved with Upgrades

- Higher gradient excitation:  $\sim 0.5 \text{ GV/m}$  in long structures.
- Acceleration of witness beam:  $\sim 100 \text{ MeV}$
- Higher RF power extraction:  $\sim \text{GW level}$




Example of 26 GHz dielectric loaded structures for two-beam-acceleration experiment:




Decelerating structure	Accelerating structure
ID / OD / length (mm)	ID / OD / length (mm)
7.0 / 9.068 / 300	3.0 / 5.025 / 300
Dielectric constant 6.64	Dielectric constant 9.70
Group velocity 0.254 c	Group velocity 0.111 c
R/Q 9.79 kΩ/m	R/Q 21.98 kΩ/m
RF power (50 nC) 1.33 GW	Shunt impedance 50.44 MΩ/m
Peak gradient 167 MV/m	$E_{\text{acc}}$ (1.26 GW) 316 MV/m
Energy loss 20.5 MeV	$E_{\text{loaded}}$ (1.26 GW) <b>267 MV/m</b>



# Layout of the ANL 26GHz 3TeV Flexible Linear Collider




# Summary of a 150 GeV Stage



# Longer Term Goal at AWA: Staging



# New scheme to avoid drive beam U-turn (using RF delay to obtain proper timing)




$\text{rf delay1}=0;$   
 $\text{rf delay2}=2L_s/c;$   
 $\text{rf delay m}=2*(m-1)*L_s/c,$   
 $m$  is the # of structures in each stage,  
 $L_s$  is the length of a single structure.

Example: Using parameters in the original design, we have 38 30cm-long structures in one module; then the shortest delay is  $2*0.3m/c = \mathbf{2ns}$ ; the longest delay is  $2* (38-1)*0.3m/c = \mathbf{74ns}$ .


In order to reduce rf losses in the delay line, let's consider the most commonly used circular overmoded waveguide w/ TE01 mode (air filled, copper wall,  $a=0.7"$ ,  $f=26\text{GHz}$ ): **delay=3.6ns/m; power loss=0.22%/m**

Then the longest delay line is  $74\text{ns}/3.6\text{ns}=\mathbf{20.6m}$

The rf loss is  $0.22\%*20.6=\mathbf{4.5\%}$



# AWA Staging Demonstration




$p_0$ (MeV/c)	$\Delta\theta$ (mrad)	$\Delta p_\perp$ (MeV/c)	$T_{rise}$ (ns)	TW Deflector Power, Length
75	34.9	2.62	50	29.6MW, 0.3m



Technology for HEP machine also have great impact in other applications: e.g. Dielectric wakefield accelerator to drive future FEL (100MeV/m, 100kHz Rep.)

DWA, 850GHz, ID=400 $\mu$ m, OD=465 $\mu$ m,  
 $\epsilon_r=3.75$ , L=10cm, TR=16.5,  $E_0=114$ MeV/m,  
Energy Gain=100MeV/m,  $P_{diss-ave}=50$ W/cm<sup>2</sup>

$$\frac{P_{main-beam}}{P_{drive-beam}} = 37.5\%$$



# Conclusion

Commissioning of the upgraded AWA Facility is underway.

The new drive beam will enable the generation of high gradient wakefields (hundreds of MV/m) and the demonstration of significant acceleration of the witness beam ( $\sim 100$  MeV).

The demonstration of staging will soon follow.

**THANK YOU FOR YOUR ATTENTION!!**

