

LLRF commissioning of the European XFEL.

RF gun and first linac RF station

Julien Branlard, for the LLRF team

IPAC 2015


Richmond VA, May 5th 2015

Talk Overview


- > XFEL accelerator and the RF gun
- > Schedule
- > Tunnel installation and commissioning
- > Closing remarks






The European XFEL: OVERVIEW



- 808 superconducting 1.3 GHz TESLA RF cavities
- 101 cryomodules (8 cavities)
- 25 RF stations (4 cryomodules)
- **1 LLRF system / RF station (i.e. per klystron)**





The European XFEL: INJECTOR




DCM: Drift calibration module
REFM: Reference synchronization and distribution
LOGM: Local oscillator generation and distribution
PZ16M: Piezo controller (16 cavities)
PSM: Power supply

The European XFEL: INJECTOR




GUN:	commissioning since	Dec. 2013
A1:	installation	May 2015
AH1:	installation	August 2015
Injector:	cool down	October 2015

The European XFEL: INJECTOR >>> FIRST BEAM <<<




10 Feb. 2015

First accelerated photo electrons at XFEL!



SCHEDULE : TUNNEL OVERVIEW



Status: 20.04.2015




MODULE TRANSPORT



MODULE TRANSPORT




MODULE TRANSPORT



SCHEDULE : TUNNEL INSTALLATION


Cold Linac Cryo Strings



Courtesy, M. Huening




SCHEDULE : BEYOND THE INSTALLATION



INSTALLATION STEPS


- Incoming inspection
- Device test
- Crate installation
- Rack installation
- Tunnel installation



INSTALLATION STEPS

> Incoming inspection

- a. Delivery
- b. Archiving of shipping documentation
- c. **Device labelling**
- d. **Database documentation**
- e. Review of the company tests (present? complete ?)
- f. **Random verification of company tests**
- g. Storage and “ready-for-test” notification
- h. Incoming inspection sheet sign off



WP02 - LLRF



 Deutsches Elektronen-Synchrotron Ein Forschungszentrum der Helmholtz-Gemeinschaft	
Title:	WP02 LLRF hardware incoming inspection sign-off sheet

Device:		Quantity:		
Order number:		Reception date:		
		OK	NOK	N/A
Shipment documentation archived		☐	☐	☐
Labelling done		☐	☐	
KDS entry done		☐	☐	
Factory tests documentation present and reviewed		☐	☐	☐
Factory tests randomly checked		☐	☐	☐
Unit #:				
Results (passed / failed) :		☐	☐	
Failure report (if failed) :				
Ready-for-test notification sent		☐	☐	☐



Incoming inspection signed-off:			
by	signature	date	
EDMS upload date:			


XFEL LLRF system installation procedure.docx

Page 9



INSTALLATION STEPS

- > Incoming inspection
- > Device test
 - a. Test stand prepared for given device and calibrated
 - b. Device is installed in test stand and test is carried
 - c. Test report is generated, stored in database
 - d. **Device is marked as tested / approved (sticker)**
 - e. Storage and “ready for installation” notification



6 ADC saturation level

ADC saturation levels at the plane of the connectors have been measured. ADCs have PASSED the tests.

Channel No.	Saturation level [dBm]	Status
1	9.277498	OK
2	9.320781	OK
3	9.299005	OK
4	9.341573	OK
5	9.125885	OK
6	9.217273	OK
7	9.101135	OK
8	9.202086	OK
9	9.076008	OK
10	9.077752	OK

Table 4: Channel saturation level at ERNI connector plane

7 ADCs spectral purity

The spurious free dynamic range has been measured. ADCs have PASSED the tests.

Channel No.	SFDR	Status
1	-107.616523	OK
2	-106.659271	OK
3	-107.851373	OK
4	-108.317389	OK
5	-108.254849	OK
6	-108.907765	OK
7	-106.718074	OK
8	-109.275238	OK
9	-107.295380	OK
10	-101.138558	OK

Table 5: ADC 1st harmonic power measurement


8 Channel-to-channel crosstalks

Channel-to-channel crosstalks have been measured. DUT has PASSED the tests.



INSTALLATION STEPS

- > Incoming inspection
- > Device test
- > Crate installation



INSTALLATION STEPS

- > Incoming inspection
- > Device test
- > **Crate installation**
 - a. Selection of components from storage
 - b. Crate infrastructure assembly
(MTCA crate , MCH, CPU, uPM), power on
 - c. Basic functionality checks
(telnet, verification of MCH settings)
 - d. Crate full population is performed
(all MTCA components)
 - e. **Basic functionality checks**
(PCIe, verification of drivers)
 - f. **Installation of servers**
(llrf, timer, MPS, watchdog, diagnostics)
 - g. Fill-in crate assembly checklist report
 - h. Storage of assembled LLRF crate
 - i. Notification “ready for cabinet assembly” is sent
 - j. Crate assembly check list uploaded in database


WP02 - LLRF




Deutsches Elektronen-Synchrotron
Ein Forschungszentrum der Helmholtz-Gemeinschaft

Title:

WP02 LLRF
MTCA crate installation check list

Destination	☐ INJ ☐ L1 ☐ L2 ☐ L3	RF station #	☐ MASTER ☐ SLAVE
CPU name			
MCH name			

	KDS number	Model
MTCA crate		☐ ELMA ☐ SCHROFF ☐ RFB

Slot	AMC	KDS #	Version	RTM	KDS #	Version
-1	uPM					
0	MCH					
1	CPU					
2	TMG					
3						
4	uTC			uVM		
5						
6						
7	uADC			uDWC		
8	uADC			uDWC		
9	uADC			uDWC		
10	uADC			uDWC		
11	uADC			uDWC		
12	uADC			uDWC		
13	uPM			uDWC		
14						
15						





Notes:

XFEL LLRF system installation procedure.docx
Page 10




INSTALLATION STEPS

- > Incoming inspection
- > Device test
- > Crate installation
- > Rack installation




INSTALLATION STEPS

- Incoming inspection
- Device test
- Crate installation
- Rack installation




LLRF rack assembly and test area (RATA)




INSTALLATION STEPS

- > Incoming inspection
- > Device test
- > Crate installation
- > Rack installation
 - a. Installation of all 19" modules
 - b. Installation of MTCA crate
 - c. Installation of all inner rack cabling
 - d. Installation of non-LLRF components
 - e. Connection to mains, to Ethernet, to water
 - f. Cabinet integral test (checklist)
 - g. Storage of cabinet in LLRF racks assembly facility
 - h. Ready for tunnel installation notification
 - i. KDS final documentation and EDMS upload of cabinet assembly checklist



INSTALLATION STEPS

- > Incoming inspection
- > Device test
- > Crate installation
- > Rack installation
 - a. Installation of all 19" modules
 - b. Installation of MTCA crate
 - c. **Installation of all inner rack cabling**
 - d. Installation of non-LLRF components
 - e. Connection to mains, to Ethernet, to water
 - f. Cabinet integral test (checklist)
 - g. Storage of cabinet in LLRF racks assembly facility
 - h. Ready for tunnel installation notification
 - i. KDS final documentation and EDMS upload of cabinet assembly checklist



INSTALLATION STEPS

- > Incoming inspection
- > Device test
- > Crate installation
- > Rack installation
 - a. Installation of all 19" modules
 - b. Installation of MTCA crate
 - c. Installation of all inner rack cabling
 - d. Installation of non-LLRF components
 - e. Connection to mains, to Ethernet, to water
 - f. **Cabinet integral test (checklist)**
 - g. Storage of cabinet in LLRF racks assembly facility
 - h. Ready for tunnel installation notification
 - i. KDS final documentation and EDMS upload of cabinet assembly checklist

WP02 - LLRF



Deutsches Elektronen-Synchrotron
Ein Forschungszentrum der Helmholtz-Gemeinschaft

Title:	WP02 LLRF cabinet installation check list
---------------	--

Destination	☐ INJ ☐ L1 ☐ L2 ☐ L3	RF station #	☐ MASTER ☐ SLAVE
Rack number			
Cooling unit	name:	IP:	

MODULE	KDS number	Notes / Comments
MTCA crate		Installation EDMS #
PSM		
PZ16M		
LOGM		
REFM		
DCM		
Eth. HUB		

Notes:



INSTALLATION STEPS

> Incoming inspection

> Device test

> Crate installation

> Rack installation

a. Installation of all

b. Installation of M

c. Installation of a

d. Installation of n

e. Connection to n

f. **Cabinet integra**

g. Storage of cabin

h. Ready for tunne

i. KDS final docum

of cabinet asse

At this point:

- ✓ Hardware checked
- ✓ Drivers installed
- ✓ Servers installed and configured
- ✓ Inner rack cabling checked
- ✓ Signal integrity verified
- ✓ Pre-commissioning DONE!

➔ **READY FOR TUNNEL
INSTALLATION**



tron

check list

☐ MASTER ☐ SLAVE

Page 12




Page 23






INSTALLATION STEPS

- > Incoming inspection
- > Device test
- > Crate installation
- > Rack installation
- > Tunnel installation
 - a. cabinet transport
 - b. RF cabling
 - c. Fiber optics connections
 - d. Connections to mains, water and Ethernet
 - e. Installation of shielding if applicable
 - f. Power ON
 - g. Installation complete checklist
 - h. Notification “system ready for commissioning”
 - i. Installation complete sign-off



INSTALLATION STEPS





COMMISSIONING

Official Approval for L1.A2 : **Apr. 20th 2015**




Coupler Processing Interlock Module



COMMISSIONING

- Subsystem integration
 - LLRF, timing, MPS, klystron
 - synchronization of triggers, gates
- RF ON
 - load / modules
- Outer rack cabling verification
 - rack-rack + rack-module
- Power calibration
 - first time using power meter
 - 1 klystron, 4 cryomodules
- Coupler re-conditioning (warm)
 - automated using FSM



COMMISSIONING REMARKS

> Installation work in parallel with RF station commissioning

- No transport (scaffolding, modules, girders...) during klystron operation
- Careful planning (schedule, shifts)

> Tunnel access

- limited space next to installed cyromodules
- keep access path free (equipment, tools, etc...)



COMMISSIONING REMARKS


> Installation work in parallel with RF station commissioning

- No transport (scaffolding, modules, girders...) during klystron operation
- Careful planning (schedule, shifts)



> Tunnel access

- limited space next to installed cyromodules
- keep access path free (equipment, tools, etc...)
- oxygen packs
- bicycle + trailer (L3: 0.5 – 1.5 km!)




> Optimizing installation granularity



SUMMARY


> Injector

- Feb. 2015: first accelerated beam!
- May-Aug. 2015: A1/AH1 installation
- Oct. 2015: injector cool down and cold commissioning



> Main linac

- May 2015: commissioning of first RF station: L1.A2
- June 2015: commissioning of L3.A6-A8
- Summer 2016: commissioning of the last RF station



> Quality control / pre-commissioning is essential

- “check as much as you can, as early as you can”

> Optimizing installation based on experience acquired with first RF station



SUMMARY

- > Thanks to all my colleagues for the hard work before, during and after installation.
- > Thank you to Dirk Noelle for the permission to use his pictures.
- > **Thank you for you attention!**
- > References:



IPAC 2012: “The European XFEL LLRF system”

MIXDES 2013: “MTCA.4 LLRF system for the European XFEL”

IPAC 2013: “Recent developments of the European XFEL LLRF system”

IPAC 2014: “The European XFEL RF gun commissioning and LLRF linac installation”