







# LC studies

## Outline:


- ILC and CLIC – project overview
- Why LCs – brief physics consideration
- Recent results
- Realization of the projects
- Summary



Steinar Stapnes, CERN  
LCC collaboration



- Electron and Positron Sources ( $e^-$ ,  $e^+$ ) :
- Damping Ring (DR):
- Ring to ML beam transport (RTML)
- Main Linac (ML) : SCRF Technology
- Beam Delivery System (BDS)




**Table 2.1.** Summary table of the 200–500 GeV baseline parameters for the ILC. The reported luminosity numbers are results of simulation [12]

Centre-of-mass energy	$E_{CM}$	GeV	200	230	250	350	500
Luminosity pulse repetition rate		Hz	5	5	5	5	5
Positron production mode			10 Hz	10 Hz	10 Hz	nom.	nom.
Estimated AC power	$P_{AC}$	MW	114	119	122	121	163
Bunch population	$N$	$\times 10^{10}$	2	2	2	2	2
Number of bunches	$n_b$		1312	1312	1312	1312	1312
Linac bunch interval	$\Delta t_b$	ns	554	554	554	554	554
RMS bunch length	$\sigma_z$	$\mu\text{m}$	300	300	300	300	300
Normalized horizontal emittance at IP	$\gamma \epsilon_x$	$\mu\text{m}$	10	10	10	10	10
Normalized vertical emittance at IP	$\gamma \epsilon_y$	nm	35	35	35	35	35
Horizontal beta function at IP	$\beta_x^*$	mm	16	14	13	16	11
Vertical beta function at IP	$\beta_y^*$	mm	0.34	0.38	0.41	0.34	0.48
RMS horizontal beam size at IP	$\sigma_x^*$	nm	904	789	729	684	474
RMS vertical beam size at IP	$\sigma_y^*$	nm	7.8	7.7	7.7	5.9	5.9
Vertical disruption parameter	$D_y$		24.3	24.5	24.5	24.3	24.6
Fractional RMS energy loss to beamstrahlung	$\delta_{BS}$	%	0.65	0.83	0.97	1.9	4.5
Luminosity	$L$	$\times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$	0.56	0.67	0.75	1.0	1.8
Fraction of $L$ in top 1% $E_{CM}$	$L_{0.01}$	%	91	89	87	77	58
Electron polarisation	$P_-$	%	80	80	80	80	80
Positron polarisation	$P_+$	%	30	30	30	30	30
Electron relative energy spread at IP	$\Delta p/p$	%	0.20	0.19	0.19	0.16	0.13
Positron relative energy spread at IP	$\Delta p/p$	%	0.19	0.17	0.15	0.10	0.07


Upgradeable to 1 GeV – parameters sets also available

### Volume 1 - Executive Summary




[Download the pdf](#)  (9.5 MB)

### Volume 2 - Physics




[Download the pdf](#)  (9.5 MB)

### Volume 3 - Accelerator




[Download the pdf](#)  (91 MB)

### Volume 3 - Accelerator



[Download the pdf](#)  (72 MB)

### Volume 4 - Detectors




[Download the pdf](#)  (66 MB)

### From Design to Reality




[Download the pdf](#)  (5.5 MB)

[Visit the web site](#)







### Drive Beam Generation


#### Drive beam time structure - initial



#### Drive beam time structure - final



e<sup>-</sup> injector,  
2.86 GeV



### Main Beam Generation Complex

# Possible CLIC stages studied in the CDR




Fig. 3.6: Simplified upgrade scheme for CLIC staging scenario B.

## Key features:

- High gradient (energy/length)
- Small beams (luminosity)
- Repetition rates and bunch spacing (experimental conditions)

Table 1: Parameters for the CLIC energy stages of scenario A.

Parameter	Symbol	Unit	Stage 1	Stage 2	Stage 3
Centre-of-mass energy	$\sqrt{s}$	GeV	500	1400	3000
Repetition frequency	$f_{rep}$	Hz	50	50	50
Number of bunches per train	$n_b$		354	312	312
Bunch separation	$\Delta t$	ns	0.5	0.5	0.5
Accelerating gradient	$G$	MV/m	80	80/100	100
Total luminosity	$\mathcal{L}$	$10^{34} \text{ cm}^{-2}\text{s}^{-1}$	2.3	3.2	5.9
Luminosity above 99% of $\sqrt{s}$	$\mathcal{L}_{0.01}$	$10^{34} \text{ cm}^{-2}\text{s}^{-1}$	1.4	1.3	2
Main tunnel length		km	13.2	27.2	48.3
Charge per bunch	$N$	$10^9$	6.8	3.7	3.7
Bunch length	$\sigma_z$	$\mu\text{m}$	72	44	44
IP beam size	$\sigma_x/\sigma_y$	nm	200/2.6	$\sim 60/1.5$	$\sim 40/1$
Normalised emittance (end of linac)	$\epsilon_x/\epsilon_y$	nm	2350/20	660/20	660/20
Normalised emittance (IP)	$\epsilon_x/\epsilon_y$	nm	2400/25	—	—
Estimated power consumption	$P_{wall}$	MW	272	364	589

Table 2: Parameters for the CLIC energy stages of scenario B.

Parameter	Symbol	Unit	Stage 1	Stage 2	Stage 3
Centre-of-mass energy	$\sqrt{s}$	GeV	500	1500	3000
Repetition frequency	$f_{rep}$	Hz	50	50	50
Number of bunches per train	$n_b$		312	312	312
Bunch separation	$\Delta t$	ns	0.5	0.5	0.5
Accelerating gradient	$G$	MV/m	100	100	100
Total luminosity	$\mathcal{L}$	$10^{34} \text{ cm}^{-2}\text{s}^{-1}$	1.3	3.7	5.9
Luminosity above 99% of $\sqrt{s}$	$\mathcal{L}_{0.01}$	$10^{34} \text{ cm}^{-2}\text{s}^{-1}$	0.7	1.4	2
Main tunnel length		km	11.4	27.2	48.3
Charge per bunch	$N$	$10^9$	3.7	3.7	3.7
Bunch length	$\sigma_z$	$\mu\text{m}$	44	44	44
IP beam size	$\sigma_x/\sigma_y$	nm	100/2.6	$\sim 60/1.5$	$\sim 40/1$
Normalised emittance (end of linac)	$\epsilon_x/\epsilon_y$	nm	—	660/20	660/20
Normalised emittance	$\epsilon_x/\epsilon_y$	nm	660/25	—	—
Estimated power consumption	$P_{wall}$	MW	235	364	589



### Vol 1: The CLIC accelerator and site facilities

- CLIC concept with exploration over multi-TeV energy range up to 3 TeV
- Feasibility study of CLIC parameters optimized at 3 TeV (most demanding)
- Consider also 500 GeV, and intermediate energy range
- <https://edms.cern.ch/document/1234244/>



### Vol 2: Physics and detectors at CLIC

- Physics at a multi-TeV CLIC machine can be measured with high precision, despite challenging background conditions
- External review procedure in October 2011
- <http://arxiv.org/pdf/1202.5940v1>



### Vol 3: "CLIC study summary"

- Summary and available for the European Strategy process, including possible implementation stages for a CLIC machine as well as costing and cost-drives
- Proposing objectives and work plan of post CDR phase (2012-16)
- <http://arxiv.org/pdf/1209.2543v1>

In addition a shorter overview document was submitted as input to the European Strategy update, available at:  
<http://arxiv.org/pdf/1208.1402v1>


Input documents to Snowmass 2013 has also been submitted:

<http://arxiv.org/abs/1305.5766> and

<http://arxiv.org/abs/1307.5288>

# Physics at LC from 250 GeV to 3000 GeV

- Physics case for the Linear Collider:
  - Higgs physics (SM and non-SM)
  - Top
  - SUSY
  - Higgs strong interactions
  - New Z' sector
  - Contact interactions
  - Extra dimensions
  - .... AOP (any other physics) ...




Specific challenges for CLIC studies:

- Need to address Higgs-studies, including gains for measurements at higher energies
- Reach for various “new physics” (list above) options; comparative studies with HiLumi LHC and proton-proton at higher energies (FCC).

New particle	LHC (14 TeV)	HL-LHC	CLIC3
squarks [TeV]	2.5	3	$\lesssim 1.5$
sleptons [TeV]	0.3	-	$\lesssim 1.5$
$Z'$ (SM couplings) [TeV]	5	7	20
2 extra dims $M_D$ [TeV]	9	12	20–30
TGC (95%) ( $\lambda_\gamma$ coupling)	0.001	0.0006	0.0001
$\mu$ contact scale [TeV]	15	-	60
Higgs composite scale [TeV]	5–7	9–12	70

Process	VLHC 200 TeV	CLIC	
		3 TeV	5 TeV
squarks	15	1.5	2.5
sleptons		1.5	2.5
$Z'$	30	20	30
$q^*$	70	3	5
$l^*$		3	5
Extra two dimensions	65	20 – 33	30 – 55
$W_L W_L$	$30\sigma$	$70\sigma$	$90\sigma$
TGC (95%)	0.0003	0.00013	0.00008
$\Lambda$ compos.	130	300	400



1.3 GHz Nb 9-cellCavities	16,024
Cryomodules	1,855
SC quadrupole pkg	673
10 MW MB Klystrons & modulators	436 *

\* site dependent


Approximately 20 years of R&D worldwide  
→ Mature technology, overall design and cost

## DESY: FLASH

- ❖ 1.25 GeV linac (TESLA-Like tech.)
- ❖ ILC-like bunch trains:
- ❖ 600 ms, **9 mA** beam (2009);      ← Demonstrated
- ❖ 800 ms 4.5 mA (2012)
- ❖ RF-cryomodule string with beam →
- PXFEL1 operational at FLASH



Xfel Prototype at PXFEL1




## KEK: STF/STF2

- ❖ S1-Global: completed (2010)
- ❖ Quantum Beam Accelerator (Inverse Laser Compton): 6.7 mA, **1 ms**      ← Demonstrated
- ❖ CM1 test with beam (2014 ~2015)
- ❖ STF-COI: Facility to demonstrate CM assembly/test in near future



S1 Global Cryomodule at STF:




## FNAL: ASTA


(Advanced Superconducting Test Accelerator)

- ❖ CM1 test complete
- ❖ CM2 operation (2013)
- ❖ CM2 with beam (soon)



CM2 at NML Facility:





2011 disassemble S1-Global,  
start construction of STF accelerator(Injector + QB)

2012 Feb: QB accelerator commissioning

Apr: beam acceleration

Jun: beam focus for Laser-Compton

Jul to Mar: experiment of Laser-Compton (QB)

2013 Apr: disassemble Laser-Compton

start installation of CM-1

Sep: two set of 4-cavity train completed


Oct: Cryomodule assembly in STF tunnel


Dec: CM-1 completed

2014 Apr: start CM-2a assembly


Jul: CM-1 and CM-2a connection will be completed

Oct: Cool-down test





CM-1



CM-2a



A High Performance cryostring

Year	Capable Lab.	Capable Industry
2006	1 DESY	2 ACCEL, ZANON
2011	4 DESY, JLAB, FNAL, KEK	4 RI, ZANON, AES, MHI,
2012	5 DESY, JLAB, FNAL, KEK, Cornell	5 RI, ZANON, AES, MHI, Hitachi

- One lab (2 vendors) in 2006
- 5 labs (5 vendors) in 2012 (maybe more)



Category	Work-base	Specific subject	Global Collaboration w/
Positron Source		Positron source	PosiPol Collaboration
Nano Beam	ATF	37 nm beam 2 nm stability	ATF collaboration
SCRF Cavity Integration	STF	Power Input Coupler Tuner He-Vessel	CERN-DESY-KEK CEA-Fermi/SLAC-KEK DESY-KEK (WS at CERN? Autumn. 2014)
CM integration	STF, ILC	Conduction-cooled SC Quadrupole	Fermilab-KEK
Cryogenics	ILC	Cryog. Underground He inventory High p. Gas Safety	CERN-Fermilab-KEK (WS at CERN, 18 June)
CFS	ILC	CFS design prep.	CERN-Fermilab-KEK
Radiation Safety	ILC	ML radiation shield	SLAC-DESY-CERN-KEK



## Parameters, Design and Implementation

- Integrated Baseline Design and Parameters
- Feedback Design, Background, Polarization
- Machine Protection & Operational Scenarios
- Electron and positron sources
- Damping Rings
- Ring-To-Main-Linac
- Main Linac - Two-Beam Acceleration
- Beam Delivery System
- Machine-Detector Interface (MDI)
- Drive Beam Complex
- Cost, power, schedule, stages

# CLIC main activities (2013-19)

## X-band Technologies

- X-band Rf structure Design
- X-band Rf structure Production
- X-band Rf structure High Power Testing
- Novel RF unit developments (high efficiency)
- Creation and Operation of x-band High power Testing Facilities
- Basic High Gradient R&D

## Experimental verification

- Drive Beam phase feed-forward and feedbacks
- Two-Beam module string, test with beam
- Drive-beam front end including modulator development and injector
- Modulator development, magnet converters
- Drive Beam Photo Injector
- Low emittance ring tests
- Accelerator Beam System Tests (ATF and FACET, others)

## Technical Developments


- Damping Rings Superconducting Wiggler
- Survey & Alignment
- Quadrupole Stability
- Warm Magnet Prototypes
- Beam Instrumentation and Control
- Two-Beam module development
- Beam Intercepting Devices
- Controls
- Vacuum Systems


## Detector and Physics

- Physics studies and benchmarking
- Detector optimisation
- Technical developments



# High-gradient accel. structure test status






Results very good, design/performance more and more understood – but:

- numbers limited, industrial productions also limited
- basic understanding of BD mechanics improving
- condition time/acceptance tests need more work
- use for other applications (e.g. FELs) needs verification

In all cases test-capacity is crucial


Previous:  
Scaled 11.4 GHz  
tests at SLAC and KEK.




NEXTEF at KEK  
ASTA at SLAC

**Clockwise from top-left:**

- Modulator/klystron (50MW, 1.5us pulse)
- Pulse compressor (250ns, ratio 2.8)
- DUT + connections
- Acc. structure (TD26CC)




Previous:  
Scaled 11.4 GHz  
tests at SLAC and KEK.




NEXTEF at KEK  
ASTA at SLAC

**Clockwise from top-left:**

- Modulator/klystron (50MW, 1.5us pulse)
- Pulse compressor (250ns, ratio 2.8)
- DUT + connections
- Acc. structure (TD26CC)




- Waveguide network connected to klystron
  - Temporary module with pulse compressor, and load for commissioning



- Diode testing has started to commission modulator
- XL5 klystron installed inside the new modulator


Previous:  
Scaled 11.4 GHz  
tests at SLAC and KEK.



NEXTEF at KEK  
ASTA at SLAC



**Clockwise from top-left:**

- Modulator/klystron (50MW, 1.5us pulse)
- Pulse compressor (250ns, ratio 2.8)
- DUT + connections
- Acc. structure (TD26CC)



- Waveguide network connected to klystron
  - Temporary module with pulse compressor, and load for commissioning

- Diode testing has started to commission modulator
- XL5 klystron installed inside the new modulator



- 4 turn-key 6 MW, 11.9942 GHz, 400Hz power stations (klystron/modulator) have been ordered from industry.
- The first unit is scheduled to arrive at CERN in October 2014. The full delivery will be completed before July 2015.



Very significant increase of test-capacity  
First commercial 12 GHz klystron systems becoming available  
Confidence that one can design for good (and possibly better) gradient performance  
As a result: now possible to use Xband technology in accelerator systems – at smaller scale

# Example: 360GeV Cost vs. Bunch Charge

Automatic procedure  
scanning over many  
structures (parameter sets)


Structure design fixed by few  
parameters


$$a_1, a_2, d_1, d_2, N_c, f, G$$

Beam parameters derived  
automatically

Cost calculated

Luminosity goal significantly  
impact minimum cost  
For  $L=1.0 \times 10^{34} \text{ cm}^{-2} \text{s}^{-1}$  to  
 $L=2.0 \times 10^{34} \text{ cm}^{-2} \text{s}^{-1}$  costs 0.5 a.u.





First to second stage: 4 MCHF/GeV (i.e. initial costs are very significant)

#### Caveats:

Uncertainties 20-25%


Possible savings around 10%

However – first stage not optimised (work for next phase), parameters largely defined for 3 TeV final stage

Beyond the parameter optimization there are other on-going developments (design/technical developments):

- Use of permanent or hybrid magnets for the drive beam (order of 50'000 magnets)
- Optimize drive beam accelerator klystron system
- Electron pre-damping ring can be removed with good electron injector
- Dimension drive beam accelerator building and infrastructure are for 3 TeV, dimension to 1.5 TeV results in large saving
- Systematic optimization of injector complex linacs in preparation
- Power consumption:
  - Optimize and reduce overhead estimates

### CERN energy consumption 2012: 1.35 TWh




#### Goal:


- Rebaseline project at ~350 GeV, ~1.5 TeV, 3 Te
- Optimised cost and power for given luminosity
- End year – hopefully needed to redo with new LHC results at some point



# CTF3 programme 2013-2016






CLIC Diagnostics tests






# CTF3 programme 2013-2016

CLIC Diagnostics tests







# CTF3 programme 2013-2016





CLIC Diagnostics tests





- First module is under test, data under evaluation
- For second and third module many components have been received
- Tunnel environment modeled in experimental hall


- Test within laboratory (tunnel model with air flow)
- Test in CTF3 with beam (earlier slide)
- Transport test



# Technology examples: Magnets and Instrumentation

## Magnet developments:

- Main Beam Quadrupole (MBQ)
- Drive Beam Quadrupoles (DBQ)
- Steering correctors



- QD0
- SD0
- Other studies (ILC and ATF studies)









Figure 1: Preliminary layout of the quadrupole magnet, arrows indicate the direction of magnetization of the permanent magnet blocks.





BI Type	CLIC-3-DB	CLIC-3-MB
Intensity	278	184
Position	46054	7187
Size	800	148
Energy (spread)	210 (210)	73 (23)
Bunch length	312	75
Beam loss / halo	45950	7790
Beam phase	208	96
Polarization		17
Tune		6
Luminosity		2



- Development of OTR/ODR simulation tools well advanced and experimental validation has already shown promising results
- Proposing future beam test at ATF2 of a combined OTR/ODR Linear collider beam size monitor
- EO SD commissioned successfully on Califes with time resolution and S/N ratio better than streak camera
- EO Transposition is currently being studied at Daresbury to provide 20fs resolution bunch length monitor
- R&D on CLIC BPMs is progressing well expecting with 2<sup>nd</sup> generation of BPM prototypes being built now
- CLIC BLM monitor are being tested intensively with the aim to select the best possible sensor with respect to sensitivity, time response and cost




Straight references





3) Use wake-field monitors accuracy O(3.5 $\mu$ m) – CTF3


1) Pre-align BPMs+quads accuracy O(10 $\mu$ m) over about 200m

2) Beam-based alignment






- Test of prototype shows
  - vertical RMS error of 11 $\mu$ m
  - i.e. accuracy is approx. 13.5 $\mu$ m






Stabilise quadrupole  
O(1nm) @ 1Hz


## FACET (Dispersion-Free Steering and Wakefield-FS)



or of 11μm  
approx. 13.5μm




More in this conference:  
THPP034 – “Experimental  
Results of Beam-based  
Alignment Tests”, A.Latina et  
al.





# Final focus: ATF 2 at KEK




Local chromatic corrections

Goal 1: demonstrate optics, tunability


Goal 2: beam stabilisation through feedback

Similar optics, similar tolerances ATF and ILC




June: reaching 44 nm, very close to ILC goal  
(37 nm corr. to 6nm at ILC)

Field quality improvements, orbit stabilisation through feedback,  
shorted turn in 6-pole magnet, beam size monitor improvements




ATF 2 Future program – next Run October

# ATF2: Stabilisation Experiment



# ATF2: Stabilisation Experiment




A.Jeremie

ATF2 operations meeting May 17 2013


In general the CLIC coll. is very interested in a longer term programme at ATF2 and ideas exist for:

- Building 2 octupoles for ATF2 (to study FFS tuning with octupoles)
- Test of OTR/ODR system at ATF2
- Test and use of accurate kicker/amplifier system is considered
- General support for ATF2 operation

# FEL linacs with SCRF modules



SLAC FNAL/ANL  
Cornell JLab




US infrastructure for  
- 35 cryomodules  
- 280 cavities  
- 4 GeV (CW)




US and EU (industrial) production  
Perfectly placed for start of ILC  
of this decade.



Largest deployment of  
this technology to date  
- 100 cryomodules  
- 800 cavities  
- 17.5 GeV (pulsed)

Kitakami  
proposed site



- Drive beam development beyond CTF3
  - RF unit prototype with industry using CLIC frequency and parameters
  - Drive beam front-end (injector), to allow development into larger drivebeam facility beyond 2018
- Damping rings
  - Tests at existing damping rings, critical component development (e.g. wigglers) ... large common interests with light source laboratories
- Main beam (see slides later)
  - Steering tests at FACET, FERMI, ...
- Beam delivery system (see slide later)
  - ATF/ATF2





- X-band technology appears interesting for compact, relatively low cost FELs – new or extensions
  - Logical step after S-band and C-band
  - Example similar to SwissFEL:  $E=6 \text{ GeV}$ ,  $N_e=0.25 \text{ nC}$ ,  $\sigma_z=8\mu\text{m}$
- Use of X-band in other projects will support industrialisation
  - They will be klystron-based, additional synergy with klystron-based first energy stage
- Started to collaborate on use of X-band in FELs
  - Australian Light Source, Turkish Accelerator Centre, Elettra, SINAP, Cockcroft Institute, TU Athens, U. Oslo, Uppsala University, CERN
- Share common work between partners
  - Cost model and optimisation
  - Beam dynamics, e.g. beam-based alignment
  - Accelerator systems, e.g. alignment, instrumentation...
- Define common standard solutions
  - Common RF component design, -> industry standard
  - High repetition rate klystrons (500Hz soon to be ordered for CLIC)



Great potential for collaboration  
(G.D'Auria et al., "X-band technology for FEL sources")

- **2013 - 2016**

- Accelerator detailed design, R&Ds for cost-effective production, site study, CFS designs etc.
- Negotiations among governments
- Prepare for the international lab.

- **2016 – 2018**

- ‘Green-sign’ for the ILC construction to be given (in early 2016 )
- International agreement reached to go ahead with the ILC
- Formation of the ILC lab.
- Preparation for biddings etc.

- **2018**

- Construction start (9 yrs)

- **2027**

- Construction (500 GeV) complete, (and commissioning start)  
(250 GeV time-scale is slightly shorter)



## Science Council

MEXT asked SCJ to evaluate ILC on four points

- 1) **Scientific significance** of the research using ILC, and the positioning of ILC project in the context of **particle physics**.
- 2) Positioning of ILC Project in the context of **overall scientific activity in Japan**.
- 3) Significance of hosting ILC for Japanese **people and society**.
- 4) **Current state of preparation and necessary conditions** for the implementation of ILC project, including securement of budget and manpower for construction and operation of ILC.



# ILC Accelerator Organization



LCC-ILC Director: M. Harrison, Deputies: N. Walker and H. Hayano


\*KEK LC Project Office Head: A. Yamamoto


Sub-Group	<u>Global Leader</u> Deputy/Contact p.	KEK-Leader* Deputy	Sub-Group	<u>Global Leader</u> Deputy/Contact P.	KEK-Leader* Deputy
Acc. Design Integr.	<u>N. Walker (DESY)</u> K. Yokoya(KEK)	K. Yokoya	SRF	<u>H. Hayano (KEK)</u> C. Ginsburg (Fermi), E. Montesinos (CERN)	<u>H. Hayano</u> Y. Yamamoto
Sources (e-, e+)	<u>W. Gai (ANL)</u> M. Kuriki (Hiroshima U.)	J. Urakawa T. Omori	RF Power & Cntl	<u>S. Michizono (KEK)</u> TBD (AMs , EU)	<u>Michizono</u> T. Matsumoto
Damping Ring	<u>D. Rubin (Cornell)</u> N. Terunuma (KEK)	N. Terunuma	Cryogenics (incl. HP gas issues)	<u>H. Nakai: KEK</u> T. Peterson (Fermi), D. Delikaris (CERN)	<u>H. Nakai</u> Cryog. Center
RTML	<u>S. Kuroda (KEK)</u> A. Latina (CERN)	S. Kuroda	CFS	<u>A. Enomoto (KEK)</u> V. Kuchler (Fermi), J. Osborne (CERN),	<u>A. Enomoto</u> M. Miyahara
Main Linac (incl. B. Compr. & B. Dynamics)	<u>N. Solyak (Fermi)</u> K. Kubo (KEK)	K. Kubo	Radiation Safety	<u>T. Sanami (KEK)</u> TBD (AMs, EU)	<u>T. Sanami</u> T. Sanuki
BDS	<u>G. White (SLAC),</u> R. Tomas (Cern) T. Okugi (KEK)	T. Okugi	Electrical Support (Power Supply etc.)	TBD	TBD
MDI	<u>K. Buesser (DESY)</u> T. Tauchi (KEK)	T. Tauchi	Mechanical S. (Vac. & others)	TBD	TBD
			Domestic Program, Hub Lab. Facilities	TBD	<u>H. Hayano</u> T. Saeki



# Site specific studies

Establish a site-specific Civil Engineering Design - map the (site independent) TDR baseline onto the preferred site - assuming “Kitakami” as a primary candidate





## Current Status: Facility Planning Progress – CFS View

Work	Underground Facilities					Surface Facilities		
	ML	AH	DR	BDS	DH	AY	CS	CC
Facility Arrangement	B/C	B/C	C	C	B/C	D	C	D
Basic Shape, Dimension	B/C	B/C	B/C	C	B/C	D	C	D
Civil/Architectural Design	C	C	C	C/D	C	D	C	D
Electronic Design	C	C	C	C/D	C	D	C	D
Mechanical Design	C	C	C	C/D	C	D	C	D

Legend: Progress degree


	Requirement	Technical Study
<b>A</b>	Clear	Completed
<b>B</b>	Clear	Under study
<b>C</b>	Unclear(50%)	Partially executed
<b>D</b>	Unclear	Not yet started

Legend: Facility

	Technical Study
<b>AH</b>	Access Hall
<b>AY</b>	Access Yard
<b>CS</b>	Central Substation
<b>CC</b>	Central Campus


## Current Status: Facility Planning Progress – CFS View

	Underground Facilities					Surface Facilities		
Work	ML	AH	DR	BDS	DH	AY	CS	CC
Facility Arrangement	B/C	B/C	C	C	B/C	D	C	D
Basic Shape, Dimension		2014	2015	2016	2017	2018		
Civil/Architectural Design		Planning	Basic Design	Detailed Design	Tendering			
Electronic Design						Cost Estimate		
Mechanical Design								



## 2013-18 Development Phase

Develop a Project Plan for a staged implementation in agreement with LHC findings; further technical developments with industry, performance studies for accelerator parts and systems, as well as for detectors.




## 2018-19 Decisions

On the basis of LHC data and Project Plans (for CLIC and other potential projects as FCC), take decisions about next project(s) at the Energy Frontier.

## 4-5 year Preparation Phase

Finalise implementation parameters, Drive Beam Facility and other system verifications, site authorisation and preparation for industrial procurement.

Prepare detailed Technical Proposals for the detector-systems.




## 2024-25 Construction Start

Ready for full construction and main tunnel excavation.

## Construction Phase

Stage 1 construction of CLIC, in parallel with detector construction.

Preparation for implementation of further stages.



## Commissioning

Becoming ready for data-taking as the LHC programme reaches completion.



# CLIC Collaboration



29 Countries – over 70 Institutes



Seven new collaboration partners joined in 2013 (The Hebrew University Jerusalem, Vinca Belgrade, ALBA/CELLS, Tartu University, NCBJ Warsaw, Shandong University, Ankara University Institute of Accelerator Technologies (IAT)).

In 2014 two (SINAP Shanghai and IPM Tehran) more

Detector collaboration operative with 23 institutes

# Collaboration

countries – over 70 Institutes



collaboration

Detector  
collaboration

Accelerator + Detector collaboration





# Key points

The ILC and CLIC accelerator studies are organised under the heading of LCC with goals:

- Strongly support the Japanese initiative to construct a linear collider as a staged project in Japan
- Prepare CLIC machine and detectors as an option for a future high-energy linear collider at CERN
- Further improve collaboration between CLIC and ILC machine experts
- Beyond the significant progress on the basic RF studies, increased and successful effort on system-studies of various types (FACET, ATF, etc)
- Many common challenges with 3<sup>rd</sup> generation light sources and FELs, the latter providing very important industrial/lab production experiences



# Thanks

- Slides/figures from LCC collaboration members and others
- Knowingly from M.Harrison, A.Yamamoto, A. Latina, K.Kubo and ATF colleagues, D.Schulte, Y.Yamamoto, W.Fang, W.Wuensch and Xband team, M. Miyahara, N.Walker, T.Lefevre, M.Modena, R.Tomas, G.D'Auria ... probably several more unknowingly