



# ATF2

## status and start of commissioning

Andrei Seryi, SLAC  
for the ATF2 team



May 8, 2009



# ATF2 team


G. Christian (ATOMKI, Debrecen), B. Parker (BNL), D. Schulte, J.-P. Delahaye, R. Tomas, F. Zimmermann (CERN), A. Wolski (Cockcroft Inst.), E. Elsen (DESY), T. Sanuki (Tohoku Univ.), E. Gianfelice-Wendt, M. Ross, M. Wendt (Fermilab), T. Takahashi (Hiroshima Univ.), S. Bai, J. Gao (IHEP Beijing), B. Bolzon, N. Geffroy, A. Jeremie (IN2P3-LAPP), R. Apsimon, P. Burrows, B. Constance, C. Perry, J. Restalopez, C. Swinson (JAI, Oxford), S. Araki, A. Aryshev, H. Hayano, Y. Honda, K. Kubo, T. Kume, S. Kuroda, M. Masuzawa, T. Naito, T. Okugi, R. Sugahara, T. Tauchi, N. Terunuma, J. Urakawa, K. Yokoya (KEK), Y. Iwashita, T. Sugimoto (Kyoto ICR), A.-Y. Heo, E.-S. Kim, H.-S. Kim (Kyungpook Nat. Univ.), P. Bambade, Y. Renier, C. Rimbault (LAL, Orsay), J.Y.Huang, S.H.Kim, Y.J.Park, W.H.Hwang ( PAL, Korea), G. Blair, S. Boogert, P. Karataev, S. Molloy, (Royal Holloway, Univ. of London), J. Amann, P. Bellomo, B. Lam, D. McCormick, J. Nelson, E. Paterson, M. Pivi, T. Raubenheimer, A. Seryi, C. Spencer, M.-H. Wang, G. White, W. Wittmer, M. Woodley, Y. Yan, F. Zhou (SLAC), D. Angal-Kalinin, J. Jones (STFC, Daresbury), A. Lyapin (UCL, London), A. Scarfe (Univ. of Manchester), Y. Kamiya, S. Komamiya, M. Oroku, T. Suehara, T. Yamanaka (Univ. of Tokyo).


and colleagues who unintentionally missed from the list




# Plan of the talk

- History and goals
- Organization
- Schedule and construction
- Highlights of recent beam runs
- Near term plans
- Longer term outlook






Extraction Line




Damping Ring

# ATF and ATF2



Control Room



Linac



# Accelerator Test Facility, KEK

1997-2008


Extraction line :utilization of low emittance beam  
beam instrumentation, collimator damage

Cavity BPM  
nanometer res.

FONT  
fast feedback ( ns )

Pulsed Laser Wire Scanner  
for beam size monitor (  $\mu\text{m}$  )

Energy: 1.28 GeV  
Electron bunch:  
 $2 \times 10^{10}$  e/bunch  
1 ~ 20 bunches/train  
3 trains/ring  
1.56 Hz





RF Gun  
multi-bunch beam

S-band Linac ( 70m )  
multi-bunch acceleration




# Low emittance in ATF



- Best measurements of emittance in ATF DR:
  - the  $\epsilon_y=4\text{pm}$  is the best achieved value at low intensity and it becomes 1.5 times at the intensity of  $1 \times 10^{10}/\text{bunch}$  [Y.Honda et al., PRL 92 (2004) 054802]
- Very recent preliminary vertical emittance:
  - the  $\epsilon_y=5\text{pm}$  (about 10% error) which was measured by Laser Wire in DR
  - thus, the best conditions are reproducible.

**ATF2**




Scaled down model of ILC final focus







# Final Focus Test Beam – optics with traditional **non-local** chromaticity compensation


~1990-1995



Achieved ~70nm vertical beam size



- The idea of **final focus with local chromatic correction** suggested in ~2000, and allowed, in particular, shortening FF of linear collider considerably
- The suggestion of a new test facility at ATF, to prototype the **final focus with local chromatic correction**, was considered in **2002** at Nanobeam workshop in Lausanne



Early scheme as presented by Junji Urakawa at Nanobeam 2002



# ATF2 major milestones


- September 2002, Nanobeam workshop, Lausanne
  - idea of new Final Focus test facility at ATF
- January 2005, SLAC, first ATF2 workshop
  - compared two optics versions, selected ILC-like design
  - stated the need to document the Proposal
- May 2005, ATF2 mtg at KEK
  - collaboration organization & MOU, task sharing, 1<sup>st</sup> version of schedule (commissioning start range: 02.2007-02.2008)
- August 2005
  - ATF2 Proposal, Vol.1 (technical description) released
- February 2006, SLAC, 1<sup>st</sup> ATF2 Project Meeting
  - ATF2 Proposal, Vol.2 (organization, cost & contributions) released
- May 2006, KEK, 2<sup>nd</sup> ATF2 Project Meeting ...
  - detailed design & role sharing
- ... May 2008, BINP Novosibirsk, 6<sup>th</sup> ATF2 Project Meeting
  - Review of construction status and commissioning readiness
- Dec 2008, KEK, 7<sup>th</sup> ATF2 Project Meeting
  - Focused on review of commissioning readiness, organization & planning

ATF2 Proposal:  
110 authors, 25  
institutions



D (μm)

# ATF2 – model of ILC BDS



## ATF2 goals

(A) Small beam size


Obtain  $\sigma_y \sim 35\text{nm}$


Maintain for long time

(B) Stabilization of beam center

Down to  $< 2\text{nm}$  by nano-BPM

Bunch-to-bunch feedback of ILC-like train







# ATF2 & ILC parameters

Parameters	ATF2	ILC
Beam Energy, GeV	1.3	250
$L^*$ , m	1	3.5-4.2
$\gamma\varepsilon_{x/y}$ , m*rad	3E-6 / 3E-8	1E-5 / 4E-8
IP $\beta_{x/y}$ , mm	4 / 0.1	21 / 0.4
IP $\eta'$ , rad	0.14	0.094
$\sigma_E$ , %	~0.1	~0.1
Chromaticity	~1E4	~1E4
$n_{\text{bunches}}$	1-3 (goal A)	~3000
$n_{\text{bunches}}$	3-30 (goal B)	~3000
$N_{\text{bunch}}$	1-2E10	2E10
IP $\sigma_y$ , nm	37	5

# ATF International Collaboration

ATF International organization is defined by  
MOU signed by 20 institutions:

CERN  
DESY  
IN2P3

Tomsk Polytechnic Univ.

INFN, Frascati

University College London

Oxford Univ.

Royal Holloway Univ.

KEK

Waseda Univ.

Nagoya Univ.

Tokyo Univ.

Kyoto Univ.

Hiroshima Univ.

PAL (Korea)

IHEP (China)

SLAC

LBNL

FNAL


Cornell Univ.

<http://atf.kek.jp/>

MOU: Mission of ATF/ATF2 is three-fold:

- ATF, to establish the **technologies** associated with **producing** the **electron beams** with the **quality** required **for ILC** and provide such beams to ATF2 in a **stable and reliable** manner.
- ATF2, to use the beams extracted from ATF at a **test final focus** beamline which is **similar** to what is envisaged at **ILC**. The goal is to demonstrate the beam focusing technologies that are consistent with ILC requirements. For this purpose, ATF2 aims to **focus** the beam down to a **few tens of nm (rms)** with a beam **centroid stability** within a **few nm** for a **prolonged period** of time.
- Both the ATF and ATF2, to serve the **mission** of providing the **young scientists and engineers** with **training opportunities** of participating in R&D programs for **advanced accelerator technologies**.


# ATF International Collaboration



ATF2 project meeting, 15-18 December 2008, KEK



# ATF International Collaboration



**Spokesperson:** direct and coordinate the work required at ATF/ATF2 in accordance with the ATF Annual Activity Plan, report the progress to ICB and the progress and the matters related to KEK budget to director of KEK (Junji Urakawa, KEK)



**ICB:** decision making body for executive matters related to the ATF collaboration (chair: Ewan Paterson, SLAC)



**TB:** assist the Spokesperson in formulating the ATF Annual Activity Plan, including the budget and beamtime allocation and assist the ICB in assessing the scientific progress (co-chairs: A.Wolski, CI, E.Elsen, DESY)



## Three Spokesperson's Deputies with for areas of:

• Beam operation:



Shigeru Kuroda  
KEK

• Hardware maintenance:

Nobuhiro Terunuma  
KEK



• Design, construction & commissioning of ATF2:



Andrei Seryi  
SLAC

## Sub-Deputies at KEK:



Toshiyuki Okugi  
KEK

Takashi Naito  
KEK




Toshiaki Tauchi  
KEK

Philip Bambade  
LAL/KEK  
acting, pending ICB approval



## Cost Breakup, 21 Dec.07



Constructed as ILC model, with in-kind contribution from partners and host country providing civil construction

Cost distribution of the components normalized by the total cost, where the in-kind ones are also included

Cost as seen at the end of 2005 (from ATF2 Proposal, Volume 2) was 5.2 Oku-yen

The 2007 cost is ~5.7 Oku-yen, partly due to increased scope (additional devices & new Extraction line)

Japanese Fiscal year	JFY2005												JFY2006												JFY2007																															
	2005						2006						2007						2008																																					
Activity	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3																				
Beam operation	ATF								ATF	ATF											ATF	ATF											ATF2																							
Conventional Facilities																						preparation					floor				utility		shie																							
Magnets									24-Q	test											5-Q, Bends (7), 6,8poles	test				Final doublet						test																								
Magnet Support									support (44)						movers																																									
Alignment																																																								
Power supplies									prototype						production																																									
QBPM									prototype	prodction-1				production-2																																										
IP-BPM									prototype						test						support s																																			
Shintake monitor (BSM)								modification to the half wavelength ; i.e. 532nm with pr																																																
Laserwire								R&D at ATF-extraction																																																
Other instrumentation																																																								
Feedforward & FONT4/5								R&D and production																																																
Vacuum																																																								
Cable plant																																																								
Control system																																																								
Installation																																																								
Funding Process										JFY2006													call for UK fund														JFY2007										JFY2008									


A decision to construct **new extraction line** was taken after the ATF2 Proposal was published.

In comparison with 2005 schedule, the actual schedule had to be **extended by several month**, to **allow construction of the new extraction line**.

Outline of ATF2 schedule, as seen at end of 2005 (from ATF2 Proposal, Volume 2)


# ILC Extraction line



- Optics of existing extraction line not suitable for beam diagnostics and coupling correction
- Large dispersion ( $\sim 2\text{m}$ ) is one of the sources of  $\epsilon$  growth
- It was redesigned and has been rebuilt




Coupling Correction /  
Emittance Diagnostics

Existing ATF Extraction Line






**New Extraction:  
 Reduced dispersion from  
 2.5m to 0.6m**





# ATF2 schedule



- **Construction of the extended shield area for final focus system can be done during the ATF beam operation.**
- Partial construction beside the current EXT line in shutdown week will release the work load for reconfiguration of the EXT line in summer of 2008.
- **ATF2 beam will come in October, 2008.**

*This slide was shown in this way ~2 years ago. The beam came in December 2008.*



# Layout & civil construction

ATF2 beam line

ATF extraction line

Final Focus System


$\beta$  matching

Diagnostic

Reconfiguration of extraction line  
for reduction of dispersion

57000

41179.42



west

Construction: new  
shielding, reinforced floor

Cooling Facilities  
for Damping Ring

6m

ATF - DR

Injection LINAC (S-band, 1.3GeV)

RF Gun

S-band Linac

Shutter

Damping Ring

Transport



# ATF2 construction in 2007

August – December



**"Assembly hall" before construction**





**"Assembly hall" emptied for construction**

Photos:  
Nobu Toge



**Construction of reinforced floor**




**Construction of shielding** ATF2



# Power Supplies and Magnet system




High Availability Power Supplies installed, connected and tested at ATF2




C.Spencer (SLAC) at IHEP, Beijing  
Dec 2005

Beamline quads: SLAC / IHEP / KEK  
design, QC / production, measurements /  
measurements & installation



天津市經緯電材有限公司





First ATF2 quad, Jan 2006




**The last regular quadrupole is going to the destination**

~20 sets of supports, movers & quads installed in January 08. R.Sugahara et al

# ilc Beamline movers




- FFTB cam movers were refurbished and used for all magnets of ATF2 (except bends)






# Advanced beam instrumentation at ATF2


- BSM to confirm 35nm beam size
- nano-BPM at IP to see the nm stability
- Laser-wire to tune the beam
- Cavity BPMs to measure the orbit
- Movers, active stabilization, alignment system
- Intratrain feedback, Kickers to produce ILC-like train





IP Beam-size monitor (BSM)  
(Tokyo U./KEK, SLAC, UK)



Laser-wire beam-size Monitor (UK group)



Cavity BPMs with 2nm resolution, for use at the IP (KEK)



C & S band Cavity BPMs, for use with Q/S magnets with 100nm resolution (PAL, SLAC, KEK)


# Magnets and Instrumentation at ATF2

22 Quadrupoles(Q), 5 Sextupoles(S), 3 Bends(B) in downstream of QM16

All Q- and S-magnets have cavity-type beam position monitors(QBPM, 100nm):

3 Screen Monitors  
Strip-line BPMs

5 Wire Scanners, Laserwires  
Correctors for feedback



Shintake Monitor ( beam size monitor, BSM with laser interferometer )

MONALISA ( nanometer alignment monitor with laser interferometer )

Laserwire ( beam size monitor with laser beam for  $1 \mu\text{m}$  beam size, 3 axes)

IP intra-train feedback system with latency of less than 150ns (FONT)




Magnet movers for Beam Based Alignment (BBA)

High Available Power Supply (HA-PS) system for magnets



# IP Beam Size monitor

- Improved with respect to FFTB Shintake BSM
  - 1064nm  $\Rightarrow$  532nm







FFTB sample :  $\sigma_y = 70 \text{ nm}$

Jul 2005: BSM arrived to Univ. of Tokyo



# BSM in Tokyo Univ.

- New optical table & laser
- New crossing angles for wider range
  - $\sigma_y$ : 37nm up to a few  $\mu\text{m}$
- sx measurement by laser wire
  - $\sigma_x$  beam size is 2.8 $\mu\text{m}$ , too large for interferometer => laser wire mode








# Beam Size Monitor


Tokyo Univ.

Shintake monitor Interferometer table on the ATF2 beam line








# C & S band Cavity BPMs



C-band dipole mode  
 Reference cavity  
 Downmix to ~25MHz  
 Digitize at ~100Ms/s, ~14 bit  
 Sub 100 nanometer resolution  
 Large dynamic range >500um





# ilc IP BPM




- Creates a reference at IP instead of opposite colliding beam
- => Need ~2nm resolution
- Challenge: ~100 $\mu$ rad angles at IP
- => Thin gap, small aperture, x-y separation


6.426 GHz (Y) and 5.712 GHz (X)

So far achieved resolution 8.7nm, dynamic range ~5 micron






# Laser wires




- Goal: non-destructive diagnostics for ILC
- (ATF2 to be tuned with carbon wires)
- Studies in ATF extraction line
- Aim to measure  $1 \mu\text{m}$  spot beam
- Aim at 150ns intra-train scan
- Located at ATF2 in a place with  $\sim \mu\text{m}$  spot
- **Presently achieved minimum beam size measurement of  $2.9 \pm 0.15 \mu\text{m}$**



Laser wire chamber at ATF, Oxford

# Fast feedback (FONT)




- At ATF2, will have ~20 bunches spaced with 150ns
- Feedback and feedforward will be used to straighten the train
- FONT4: latency estimate
  - Irreducible latency: 14ns
  - Electronics latency: 118ns
  - Total latency: 132ns


FONT – Feedback On Nanosecond Time scale  
 the group initially developed analog feedbacks  
 with ~25ns latency.

Developments for ATF – digital, FONT4

# ilc FD integration

Stability study and integration of Final Doublet at LAPP, Annecy





FD alignment after the  
Radiation Inspection ,  
11 December, 2008



From QD20X  
to the dump



# Organization of ATF2 Commissioning

- Organization of commissioning was major focus of 7<sup>th</sup> ATF2 project meeting on Dec 2008
- Aim to achieve reliable observation of design beam size by end of 2010
- Overall principles
  - Integration of commissioning efforts for the whole collaboration
  - Importance of longer term plan, intermediate milestones (goals of each run) and detailed schedules of each run
  - Move from doing a collection of individual R&D tasks to focus on a common goal
  - Dedicate 50% of time to ATF2 programs
- Global milestones and detailed schedule developed internally by the ATF collaboration




# Highlights of recent runs

- **December 2008 pilot run**
  - large IP beta optics, semi-ballistic trajectory
  - Establish beam to beam dump, minimize losses, Radiation inspection
  - First tests of hardware and tuning software (FS)
  - BSM commissioning & background characterization
- **Jan 2009**
  - Continue hardware commissioning & fast kicker study
  - Replace QM7 to one with larger aperture (possible source of EXT  $\epsilon$  growth)
- **Feb-Mar 2009**
  - Large (8cm beta\*), all magnets ON
  - Continue hardware commissioning
  - Commission laser wire mode of BSM
  - Tuning tools (EXT disp./coupling corr., IP scans,  $\beta/\eta$  &  $\epsilon$  determ, BBA)
- **Current April 2009 run**
  - Optics verification for  $\sim 1\mu\text{m}$  beam (large, 1cm  $\beta^*$ ) / IP wire scanners
  - Commission interferometer mode of BSM



# Feb-Mar run highlights


## BSM Compton signal in LW mode



Convolutated size of 13microns was measured



# Mover & corrector based automated calibration of BPMs







# Feb-Mar & Apr run highlights



## EXT coupling correction

## Optics tools



- Vertical emittance scans using 2 available skew quads
- Emittance measurement using 5 vertical wire scanners

- Can verify and correct optics
- DR to EXT well matched,  $BMA G_y \sim 1.04$



● Laser on  
■ Laser off

- BSM: 8 deg mode
- Can observe the signal from the start
- Continue working on laser and optics, to achieve beam size and see it by BSM



# Long term plans

- As discussed at 7<sup>th</sup> ATF2 project mtg
- Long term plans
  - Stabilization to nm beam position, Monalisa
  - smaller beta\*
  - SC FD
- Much longer Term Plans after ~2012, very tentative
  - Optional Photon facility ; 2015 – 2019
    - laser and optical cavities for photon linear collider
    - generation of photon beam
  - "Strong QED" experiments with Laser
    - Non-linear QED with Laser intensity of  $> 10^{22}$  W/cm<sup>2</sup>
    - Unruh radiation study





# ilc IP Interferometer

Monitoring Alignment &  
Stabilisation with high Accuracy


MONALISA Oxford

- MONALISA: measures 6D position of two objects separated by several meters with a precision of nanometres using interferometers
- Expect resolution:  $\sigma_y$ :10nm, distance: 1m
- Use FFI and FSI (Fixed Frequency and Frequency Scanning Interferometry)
- Measure position of FD with respect to Shintake monitor








# SC Final Doublet for ATF2




Brett Parket, et al, BNL





# ATF2 Outlook





# Conclusion

- ATF collaboration has completed construction of ATF2 facility and has started its commissioning
- ATF collaboration is streamlining organization of commissioning to match the challenge and the timescale
- Hardware for the second goal of ATF2 is being developed
- Looking into the future, planning upgrade of ATF2
- Tentative long term plans are being developed