

First Lasing of the *LCLS* X-Ray FEL at 1.5 Å




May 4-8, 2009

Paul Emma, for the *LCLS* Commissioning Team



SLAC *National Accelerator Laboratory*



Planned/Proposed Hard X-ray FELs

- *Euro X-FEL* at DESY (0.1-6 nm)
- *SCSS* at Spring8 in Japan (0.1-3.6 nm)
- *PSI-FEL* in Switzerland (0.1-7 nm)
- *LCLS* at SLAC in USA (0.15-1.5 nm)



...and many soft x-ray FELs taking shape around the globe

This talk will concentrate on *LCLS*, with first lasing and FEL saturation at 1.5 Å...

Linac Coherent Light Source at SLAC

X-FEL based on last 1-km of existing 3-km linac

Proposed by C. Pellegrini in 1992

1.5-15 Å
(14-4.3 GeV)

Injector (35°
at 2-km point

Existing 1/3 Linac (1 km)
(with modifications)

New e^- Transfer Line (340 m)

X-ray
Transport
Line (200 m)

Undulator (130 m)

Near Experiment Hall

Far Experiment
Hall




UCLA




LLNL




Commissioning Status of *LCLS*

- Laser, gun, & injector commissioned: 2007
- Linac & bunch compressors commissioned: 2008
- First beam through undulator beamline: Dec. 2008
- 21 undulator magnets installed & ready: April 7, 2009
- First lasing at 1.5 Å: April 10, 2009 (first try!) 
- 1.5 Å FEL saturation observed: April 14, 2009 (after BBA)
- X-ray diagnostics hall is not ready until early June
- Temporary (makeshift) x-ray diagnostics used up to now
- User operations start in Sep. 2009



25 undulators
installed...
8 more to go




Undulator Gain Length Measurement at 1.5 Å: 3.3 m



Injector Transverse Projected Emittance $< 0.5 \mu\text{m}$

Exceptional beam quality from S-band Cu-cath. RF gun...



Time-sliced emittance: $0.3\text{-}0.4 \mu\text{m}$



135 MeV


0.25 nC

35 A



D. Dowell


Undulator 'Taper Scan' Shows 1.1 mJ per X-ray Pulse




1.5 Å

Pixel sum of x-ray YAG screen CCD camera vs undulator K-taper



4.6 MeV at 0.25 nC = 1.1 mJ or 0.8×10^{12} photons/pulse (15 GW at 75-fs FWHM pulse length)




LCLS Machine Layout




- Accelerator is last 1-km of SLAC linac (14 GeV)
- RF photocathode gun and off-axis injector
- Two bunch compressors + 'laser heater'
- Two transverse RF deflectors for time-resolved beam measurements
- X-band (12 GHz) compression linearizer
- 4 emittance diagnostic stations + 4 spectrometers
- Primary and secondary collimation sections
- Fixed gap, planar, 132-m undulator at 14 GeV + 1- μm res. RF BPMs
- Near and Far Experimental Halls + 500 m of x-ray transport




adds Landau damping



Laser Heater Working Well
see WE5RFP041






Thanks Michael Borland!



Laser Heater Improves FEL Power


FEL Gain:



12 undulators inserted
(FEL not saturated here)

preliminary

Undulator Girders with 5-DOF Motion Control + IN/OUT



Beam Finder Wire (BFW)

Cavity BPM ($<0.5 \mu\text{m}$)

Quadrupole magnet

3.4-m undulator magnet

sand-filled, thermally isolated supports

beam direction

X-translation (in/out)

Wire Position Monitor


Hydraulic Level System

CAM-based 5-DOF motion control

Beam-Based Undulator Alignment


- Measure undulator trajectory at 4 energies (4.3, 7.0, 9.2, & 13.6 GeV)
- Scale all linac & upstream transport line magnets each time
- Do not change anything in the undulator
- Calculate... (*Matlab* GUI)
- Move quads and adjust BPM offsets for dispersion free trajectory
- Iterate...

H. LOOS




Undulator Quadrupole Alignment after BBA

- Vary each quadrupole magnet gradient by 30% sequentially
- Record kick angle using both upstream & downstream BPMs, adjusting for incoming jitter
- Calculate quadrupole magnet transverse offsets




<1 μm Undulator Quadrupole Remote Position Control

3-parameter fit to 20 BPMs along undulator (y_0 , y'_0 , and $\Delta y'$)



$\pm 4 \mu\text{m}$




<0.5 μm res.
S. Smith
TU3GRC05

Beam Finder Wire – Aligns 'Loose' End of Undulator


BFW

Also used to measure emittance in undulator

wire IN





wire OUT



nominal chamber





wire target

beam direction






pumpout

Bunch Compression & CSR Measured after BC2 (0.25 nC)



Measuring Bunch Arrival Time Jitter with an RF Deflector




$\Delta t \approx \pm 0.6 \text{ ps}$

$9 \mu\text{m rms}$




$110 \mu\text{m rms}$

Timing Jitter = $(110 \mu\text{m}) / (2.34 \text{ mm/deg}) = 0.047 \text{ deg} \Rightarrow \underline{\underline{46 \text{ fsec rms}}}$

Feedback Systems - Bunch Length & Energy (6x6)




Charge feedback: $Q = 0.25$ nC




Measurements and Simulations for 20-pC Bunch at 14 GeV



MEASURED SLICE EMITTANCE



SIMULATED FEL PULSES




Simulation at 1.5 Å based on measured injector & linac beam & *Elegant* tracking, with CSR, at 20 pC.




Simulation at 15 Å based on measured injector & linac beam & *Elegant* tracking, with CSR & 20 pC.

Commissioning Time-Line

- Commissioning
- Project Milestones
- Installation Periods



Acknowledgements



Thanks to...

- The extraordinary commissioning team at **SLAC**!
- The operations, metrology, engineering, controls, installation, and RF groups at **SLAC**
- The tremendous undulator and cavity-BPM team at **ANL** – GREAT JOB! 
- **John Galayda** (project director) for his leadership and confidence in the team
- And many of **you**, who have contributed your ideas, comments, codes, and many years of experience toward the design and operation of this revolutionary new light source – 17 yrs later