

The Status of the Fermilab Main Injector Project,

D. BOGERT, W. FOSTER, W. FOWLER,
S. HOLMES, G. JACKSON, P. MARTIN,
T. PAWLAK, Fermilab* - The Fermilab Main Injector

is a new 150 GeV synchrotron now in the fourth year of a scheduled seven year funding profile. An R&D program has been completed, and both civil construction and the production of technical components are well underway. The Main Injector Project is part of a larger upgrade program at the Fermi National Accelerator Laboratory called Fermilab III which is designed to ensure a Collider luminosity in excess of $5 \times 10^{31} \text{ cm}^{-2} \text{ sec}^{-1}$, while simultaneously providing a 2 microAmp resonantly extracted 120 GeV beam. The 120 GeV beam will provide unique capabilities in the realm of rare neutral K decays and long baseline neutrino oscillation experiments. The expected performance characteristics of the Main Injector will be discussed, and the status of the construction and the schedule for completion will be reviewed.

* Operated by Universities Research Association, Inc., under contract with the U.S. Department of Energy.