

# STATUS OF THE RF SYSTEMS FOR THE SPIRAL2 LINAC AT THE BEGINNING OF THE CONSTRUCTION PHASE

Marco Di Giacomo, Bernard Ducoudret, Michel Tripon, Gwenal Le Dem, P. Barret (GANIL, Caen), Philippe De Antoni, Philippe Galdemard, Michel Luong, Olivier Piquet (CEA/DSM/ DAPNIA, Gif-sur-Yvette)

## Abstract

The Spiral 2 project [1] uses a RFQ and a superconducting linac to accelerate high intensity beams of deuterons and heavier ions. The accelerator frequency is 88 MHz. The construction phase was approved in Mai 2005 and the project organization was recently finalized. The RF Systems include power amplifiers and control electronics for the entire accelerator and some of the RF devices on the beam line: the slow and fast chopper and the rebunchers. The paper describes the status of the amplifiers prototypes, the architecture chosen for the digital LLRF and the preliminary studies on the other RF devices.

CEA/DAPNIA of the control electronics, INFN/LNS is in charge of the slow chopper.

## BEAM LINE DEVICES

### The Slow Chopper

Requirements for the slow chopper have been established very recently and there are dominated by the ion beam dynamics with a bunch diameter of 62 mm. This figure leads to quite big plates whose geometry still has to be studied. Table 1 summarizes the main requirements.

Table 1: Slow chopper requirements

Deflecting voltage	$\pm 5$ kV
Deflecting length	160 mm
beam radial dimension (radius)	31 mm
Pulse length	100 $\mu$ s $\div$ 1s
Pulse rise time	< 100 ns
Pulse repetition rate	> 20 Hz

## INTRODUCTION

According to the organisation of the accelerator division, the tasks of the *RF System* group include the supply of the power amplifiers and control electronics for the entire accelerator and of some of the RF devices on the beam line: the slow and fast chopper and the normal conducting rebunchers. All this equipment is schematised in figure 1, where the RFQ resonator and the cryomodules with the superconducting cavities are greyed as other groups are in charge of them.. Since the beginning, the SPIRAL 2 project is based on a large national and international collaboration. In the case of the RF systems, various laboratories already participate from the design to the commissioning of the different components: GANIL is in charge of the power amplifiers, the rebunchers and the fast chopper,

### The Beta 0.04 Rebunchers

The MEBT line, is equipped with 4 rebunchers whose parameters already include the future possibility to accelerate  $A/q=6$  ions. The required voltage is 165 kV but, due to the high beam aperture, the Transit Time Factor (TTF) is quite low and a much higher voltage on the gap is required. To keep the longitudinal length of the cavity as small as possible, a 3 gap structure has been chosen.




Figure 1: The RF Systems of the driver accelerator and of the high energy beam line.

The double quarter wave resonator of figure 1 is proposed instead of the classical split ring cavity. The stems can be manufactured and cooled more easily, and the gap geometry is better guaranteed. According to the preliminary thermal calculations, the displacement of the electrode can be kept below 0.2 mm. Thermal detuning will be compensated by a side plate with a stroke of 15 mm. The coupler is inductive and placed on the bottom of the cavity. The half height of the cavity is around 606 mm with a slight unbalance to compensate the presence of the coupling loop. Table 2 summarises the main parameters of the cavity.

Table 2: Parameters of the rebuncher cavity

Electrode voltage	102 kV
Beam aperture diameter	60 mm
TTF	0.39
Q	5600
Power consumption	11 kW
Max E field	10.2 MV/m
Max H field	9200 A/m
Flange to flange distance	300 mm

*The Fast Chopper (Bunch Suppressor)*

A fast chopper is required to isolate bunches and study the reaction issued by only one bunch on the target. The following parameters based on SNS values have been recently fixed but the feasibility has still to be studied, the frequency, the beta and the beam dimensions being significantly different.

Table 3: Requirements for the fast chopper

Deflecting voltage	$\pm 2.5$ kV
Deflecting length	450 mm
Deflecting section aperture	26 mm
Isolated bunch repetition rate	1:100 to 1:10000
Pulse rise/fall time	< 5 ns

**POWER AMPLIFIERS**

*RFQ Amplifier*

The last tests on the RFQ prototype have confirmed a Q factor about 10% lower than expected. Therefore, we can consider that the final cavity will require around 160 kW with a beam loading of few kW for ion operation voltages. Then, a total power of 200 kW has to be available at the amplifier. This power level is absolutely unusual at 88 MHz and we found only one manufacturer who could propose us a two stage tube amplifier, based on the TH 781 (250 kW) and TH 343 (20 kW) tetrodes, but whose cost is very high, being a single masterpiece. This considerations, associated to the parallel request from the RFQ group to drive the cavity keeping the four quadrant symmetry, lead to the scheme in figure 2. Four smaller amplifiers are coupled directly through the cavity, using four input ports placed at the same longitudinal position and one per quadrant to assure the polar symmetry. Four circulators

are used to isolate the amplifiers and avoid oscillation problems. The I/Q modulators before the amplifiers compensate the gain and phase differences between the different branches. Four feedback slow loops could also be added if needed.




Figure 2: 4 Amps plus circulators scheme.

Standard FM amplifiers are much less expensive but limited to 30 kW. Only one triode is used, the first stage being solid state. A 40 kW prototype, based on the same technology but using a more powerful tube (3CW 40000) was bought for the coupler test bench but it appeared to be unreliable when used at maximum power. Considering the encouraging results recently obtained with solid state modules at SOLEIL [2], we are still studying whether a solid state solution couldn't be more interesting both on the cost and the reliability aspects.

*Solid State Amplifiers*

10 and 20 kW units are required for the 2 families of the SC linac. The FM technology has strongly progressed these last years and standard solid state amplifiers are now available at this power level. Water cooling has been required with respect to the standard FM technology, to simplify the maintenance of the cooling equipment, to increase the Mean Time Between Failure (MTBF). Each amplifier is equipped with an external circulator and dummy load to sustain mismatched operating conditions. This solution was preferred to the use of distributed circulators at the output of the transistors as it is less expensive, sustains higher SWVR and protects the combiners and the transmission lines too. The first prototypes of the amplifiers and of the circulators should be ready by the end of the year.

A 20 kW test bench able to produce all SWVR conditions has being studied and is being assembled at Ganil and will be used for the amplifiers and circulators commissioning, the first prototypes of which should be delivered by the end of the year.

**LLRF**

*General Architecture*

Since the beginning, a digital LLRF (DLLRF) has been chosen because of the advantages in terms of

