

CURRENT STATUS OF L-BAND ELECTRON ACCELERATOR FOR IRRADIATION SOURCE*

S. H. Kim[#], H. R. Yang, M. Cho, and W. Namkung
Department of Physics, POSTECH, Pohang 790-784, Korea

S. D. Jang, Y. G. Son, S. J. Kwon, S. J. Park, and J. S. Oh
PAL, POSTECH, Pohang 790-784, Korea

Abstract

An intense L-band electron accelerator is designed and under development for CESC (Cheorwon Electron-beam Service Center) irradiation applications. It is capable of producing 10-MeV electron beams with average 30 kW. For an RF source, a Thales klystron is used with 1.3 GHz, pulsed 25 MW, and average 60 kW. The accelerator column, fabricated by IHEP in China, is operated with $2\pi/3$ mode traveling-wave under the fully-beam-loaded condition. The modulator was fabricated with inverter power supplies. The klystron was assembled to the klystron tank with pulse transformer. The high-voltage pulse test was conducted for the klystron tube. In this paper, we present design details of the accelerator and current status.

INTRODUCTION

Recently, demands on the electron linear accelerator are increased for industrial applications [1]. In using electron as an irradiation source, the higher beam energy is favorable since the penetration depth is larger, as shown in Figure 1. However, the electron beam energy is limited by about 10 MeV due mainly to neutron production. For the clinical X-ray systems, a low current and a low repetition rate are required. The X-ray source for the container inspection requires 5-10 MeV with a few kilowatts of the average beam power [2]. On the other hand, the food or waste sterilization system requires relatively high average beam power since the process speed is proportional to it [3].

A high average-power electron accelerator is being developed in the institutional collaboration of between PAL/POSTECH and KAPRA. The accelerator will be installed at CESC and it will be used for not only for sterilizing foods and medical products, but also reforming materials. The accelerator is required to provide an average beam power of 30 kW at the beam energy of 10 MeV. In order to achieve such a high beam power, the RF frequency is determined as 1.3 GHz for a higher pulsed RF power. Since the beam current is also high, the L-band travelling-wave accelerating structure is designed with the beam-loading effect.

*Work supported by KAPRA.

[#]khan777@postech.ac.kr




Figure 1: The depth-dose curve for electron beam. The “double” means that the beam is also injected from opposite side.

ACCELERATOR SYSTEM

The accelerator system is mainly divided by a power supply part, a RF system, and a beamline. Components, inside the hashed boxes in Figure 2, are the power supply parts. They supply high-voltage or high-power to the klystron and the E-gun. To supply a 264-kV beam voltage with a beam current of 230 A to the klystron tube, a pulse modulator and a pulse transformer is developed by PAL. The modulator mainly consists of a set of inverter power supplies, a pulse forming network (PFN), and a thyatron switch. The inverter power supplies are totally 8 units, each of 45 kV and average 30 kW. The PFN has 15 stages, each with a 50-nF capacitor and a 2.2- μ H inductor. CX2412X is used for the thyatron switch. The pulse length is 10 μ s and the repetition rate is 350 Hz, as presented in Table 1.

The RF-line includes the klystron (Thales TV2022D) and waveguide network. The klystron amplifies the RF power to pulsed 25 MW from the source RF generator of 1.3 GHz. It delivers RF to the accelerating column through the L-band waveguide network. Since the column is a travelling-wave structure, the matched load is attached after the output of the column. Since the pre-buncher needs a few kilowatts of RF power, the coaxial line is branched from the waveguide line, by amount of -38 dB.




Figure 3: The temperature of the accelerating column with the cooling water.

STATUS AND PLAN

The fabrication of the modulator was finished and the klystron tube was assembled to the tank. The high-voltage pulse test is conducted for the klystron tube, early in the June. The result is presented in Figure 4. The PFN will be tuned to get the even flat top and enough flat top width.

The accelerating column will be delivered soon, and then other beamline components will be assembled to the accelerating column. The waveguide and coaxial line is ready to be installed at CSEC. The installed high-power RF system in the CESC site is shown in Figure 5.

The beam scanner, cooling system, and control system under development in parallel. The beam commissioning is planned to be conducted in this year.




Figure 4: The high-voltage pulse test for the klystron tube.

ACKNOWLEDGEMENT

The authors are appreciated to Prof. Luo Yingxiong at IHEP, Beijing for useful discussions on general issues of the accelerator system and the design of the accelerating column.

REFERENCES

- [1] A. M. M. Todd, "Emerging Industrial Applications of Linacs," in Proc. Intl. LINAC Conf. (Chicago, IL, August 23-28, 1998), 1036 (1998).
- [2] V. Pirozhenko, V. Belugin, A. Mischenko, N. Rozanov, B. Sychev, V. Vetrov, Y. Kokorovets, V. Ryzhikov, N. Shumeiko, S. Yatsenko, A. Korolev, K. Simonov, V. Eylan, "Complex for X-ray Inspection of Large Containers," in Proc. of EPAC 2006 (Edinburgh, Scotland, June 26-30, 2006), 2388 (2006).
- [3] Y. Kamio, "10 MeV 25 kW Industrial Electron Linacs," in Proc. Int. Linac Conf. (Geneva, Switzerland, Aug. 26-30 1996), 836 (1996).
- [4] S. H. Kim, B. Park, S. I. Moon, H. R. Yang, S. D. Jang, Y. G. Son, S. J. Park, J. S. Oh, M. H. Cho, and W. Namkung, J. Korean Phys. Soc. **50**, 1416 (2007).




Figure 5: The drawing of the accelerator setup at the CSEC site and picture of the installed high-power RF system.