

# RF structures for Linac4

F. Gerigk, N. Alharbi, M. Pasini, S.  
Ramberger, M. Vretenar, R. Wegner


PAC'07, Albuquerque, USA



Since last week Linac4 is an approved project!




Since last week Linac4 is an approved project!




Now it is time to deliver!

# Motivation




- Linac4 will enable the CERN proton injector chain to reach the “ultimate” LHC luminosity,
- Linac4 will inject at 160 MeV into the PS Booster (PSB) → increase  $\beta\gamma^2$  by a factor of 2 → double the number of particles per cycle (TUPAN109, TUPAN093)
- as PSB injector Linac4 will operate at low duty cycle (<0.1%),
- Linac4 is also designed to become the front end of the SPL, a multi-GeV, multi-MW H<sup>-</sup> linac, which will operate at a duty cycle of  $\approx 5\%$ ,
- while the accelerating structures and klystrons are designed for 5% duty cycle the Linac4 infrastructure (klystron modulators, cooling water, electrical station, etc) is only designed for 0.1% and will then be upgraded.


# Linac4 machine layout




## Linac4 as PSB injector (0.1% duty cycle)




# Linac4 machine layout




## Linac4 as PSB injector (0.1% duty cycle)





## Linac4 as SPL injector (5% duty cycle)




# Site layout SPL



# Linac4 layout



# Accelerating structures




Final round of optimisations is now finished → design frozen!

All structures have been re-assessed and the overall approach was revised.

## Latest optimisation:


- decrease safety margin on LEP klystron operation (0.8 MW → 1.0 MW, max. power: 1.3 MW, CW), maintaining 80% of Superfish  $ZT^2$ ,
- shift in transition energies:
  - DTL/CCDTL: 40 to 50 MeV,
  - CCDTL: 90 to 102 MeV,
- exchanged the SCL (90-160 MeV) with a  $\pi$ -mode structure (102 - 160 MeV)
  - one single frequency (352 MHz).

# Shunt impedadance




DTL with PMQs:

➔ high  $ZT^2$  but not flexible,



# Shunt impedence




DTL with PMQs:

➔ high  $ZT^2$  but not flexible,


CCDTL with ext. EMQs:

➔ high  $ZT^2$  and flexible,

➔ cannot be used  $< 40$  MeV,



# Shunt impedence




DTL with PMQs:

➔ high  $ZT^2$  but not flexible,

CCDTL with ext. EMQs:

➔ high  $ZT^2$  and flexible,


➔ cannot be used  $< 40$  MeV,



**90/100 MeV to 160 MeV:**

**SCL:**  $\pi/2$  mode structure at 704 MHz: 4 modules with 5 coupled cavities (21 cells each!): 468 cells!

# Shunt impedence




DTL with PMQs:

➔ high  $ZT^2$  but not flexible,

CCDTL with ext. EMQs:

➔ high  $ZT^2$  and flexible,

➔ cannot be used  $< 40$  MeV,






**90/100 MeV to 160 MeV:**

**SCL:**  $\pi/2$  mode structure at 704 MHz: 4 modules with 5 coupled cavities (21 cells each!): 468 cells!

**PIMS:**  $\pi$  mode structure at 352 MHz: 12 cavities with 7 cells each: 84 cells (+3 CCDTL tanks)




# Accelerating structures: RFQ



## RFQ:

- nominal solution: IPhi RFQ (CW, 100 mA,  $P_{av}=300$  kW), under development at CEA,
- a scaled down version ( $P_{av}=10$  kW) is under study at CERN,
- 3 m instead of 6 m, simplified cooling, simplified construction,


# Accelerating structures: DTL



## DTL:

- 3 tanks, 3 - 50 MeV,
- ITEP, VNIIEF, Russia: PMQs, drift tubes,
- revised hot prototype under development at CERN,
- cold model under construction (KASCT, Saudi Arabia),


# Drift tube prototype (VNIIEF)



Evacuation channel

Bellow

Cooling channel





Permanent magnet



Laser weldings

# PMQ ITEP prototype

PMQ made of SmCo5, constructed to specifications, measured at CERN





# Accelerating structures: CCDTL






## CCDTL prototyping:

- under development at CERN since ~5 years,
- CERN hot model with 2 half cavities and one coupling cell was high-power tested,
- BINP/VNIITF hot model with 2 full cavities and 1 coupling cell is high-power tested this week,


# CCDTL module: 3 cavities



# CERN prototype: 2 half-cavities




# BINP/VNIITF prototype: 2 full cavities





- field flatness error < 1%,
- surface roughness: 1.3  $\mu\text{m}$ ,
- 90% of theoretical Q value (36200),
- vacuum quality depends on Helicoflex joints,

# BINP/VNIITF prototype: 2 full cavities




# Accelerating structures: PIMS





## PI-mode structure (PIMS):



- 7-cell pi-mode cavities at 352 MHz,
- scaled ( $\beta$ ) version of the LEP NC accelerating structure,
- in operation at CERN until 2000,
- cold and hot prototype under development.




# Accelerating structures: PIMS



7-cell structure




different coupling slot geometries



# Structure parameters

|                     | DTL  | CCDTL | PIMS |
|---------------------|------|-------|------|
| output energy [MeV] | 50   | 102   | 160  |
| cavities            | 3    | 7 x 3 | 12   |
| peak power [MW]     | 4.7  | 7     | 11.3 |
| movable tuners      | 8    | 9     | 24   |
| length [m]          | 18.7 | 25    | 22   |




● 1.3 MW klystron (LEP, CW)

● 2.5 MW klystron (pulsed)

■ Modulator for 1.3 MW RF

■ Modulator for 2.5 MW RF

# summary



- Linac4 is approved!
- The final round of structure optimisations is completed.
- Prototyping for all structures is in progress.
- Civil engineering plans ready by August.
- Next year we will start to dig!!