

*Particle Accelerator Conference
Albuquerque, New Mexico June 28, 2007*



RF SOURCE FOR THE ILC

Adam Balkcum and Thomas Habermann
CPI MPP Division, Palo Alto, CA U.S.A.



Prototype Klystron



- VKL-8301 MBK developed for DESY X-FEL / TTF project
 - ❑ vertical prototype delivered to DESY in March 2005
 - ❑ uses six electron beams set on a large bolt circle for reduced cathode loading and longer life
 - ❑ considered one of the baseline sources for the ILC






Measured Performance




Test Results Compared to Klystron Specification

<u>Parameter</u>	<u>Measurement</u>	<u>Specification</u>
Frequency	1.3 GHz	1.3 GHz
Peak Power Output	10 / 9 MW*	10 MW
Ave. Power Output	150 kW	150 kW
Power Asymmetry	0.7 %	≤ 5 %
Efficiency	59 / 55 %*	65 % (goal)
Beam Voltage	120 kV	≤ 120 kV
Beam Current	141 A	≤ 150 A
Microperveance	3.4	≤ 3.6
RF Pulse Length	1.5 ms	1.5 ms
Saturated Gain	49 dB	≥ 47 dB
Cathode loading	2.2 A/cm ²	---
Body Current (DC)	0.6 A	---
Body Current (Sat)	3.6 A	---

Power vs Frequency



Power vs Drive



* Lower power and efficiency were measured at DESY



Horizontal Prototype MBK



- Order received from DESY for second MBK for European X-FEL
 - ❖ horizontally oriented to fit in tunnel
 - ❖ includes integrated frame assembly for ease of movement and attachment to pulse transformer tank
 - ❖ includes integral lead shielding and cathode socket
 - ❖ above features are also appropriate for ILC source

- Design effort currently underway
 - ❖ prototype delivery scheduled for next summer
 - ❖ implementing some ideas for cost reduction identified in ILC cost study



ILC Cost Study Report



- CPI MPP participated in the ILC industrial cost study program for the Americas region
 - estimates provided for labor and material costs for quantities 1, 250 and 750
 - facilitization costs also estimated (space requirements, fixtures, equipment, energy, industrial gases, etc.)
- Ideas for cost reduction explored
- Cost estimate meets $\pm 20\%$ requirement



Cost Study Methodology




- **Material**
 - ❖ majority of bill of material well established
 - ❖ multiple supplier quotes for individual piece parts in quantities
 - ~20 core suppliers
 - learning curve sanity check
 - ~80% of bill costed, ~20% estimated
- **Labor**
 - ❖ hours from previous build as baseline
 - ❖ estimates of savings from simplifications
 - ❖ learning curves applied for large quantities
- **Facilities**
 - ❖ examined current loading and cost rates to extrapolate requirements for peak production (1.7 and 5 per week)
- **Experience with recent successful large klystron production program for the SNS project used for comparison**



Direct Mat'l & Labor Cost Summary



Relative Costs for Qty 1



- Major cost areas identified
 - simplify RF circuit & solenoid
 - DFA / DFM for reduced engineering hours



Cost Study Conclusions



- Substantial (~20%) direct labor and material savings possible with design changes
 - DFA / DFM to simplify assembly and reduce parts count
 - alternative circuit configuration to reduce klystron and solenoid size
- Facilities investment to support peak production years
 - modest for qty 250 (a test stand & exhaust station)
 - much larger for qty 750 (several test stands, exhaust stations, furnaces, space)
- Facilities cost reduction through equipment loans
 - e.g., use of modulators & test equipment that can then ship with last klystrons for use on the accelerator
 - approach successfully used on other large scale production programs (e.g., XM Radio)