

***THE CORNELL ERL
S.C. INJECTOR
TEST CRYOMODULE***

Matthias Liepe

Department of Physics, CLASSE


Cornell University



A 100 mA SRF Injector Cryomodule for the Cornell ERL X-ray Light Source

Cornell ERL:


5 GeV, 100 mA





Injector Beam Requirements and SRF Answers

- $E = 5-15 \text{ MeV}$
- beam power $\leq 0.5 \text{ MW}$
- max current 0.1 A 
- $q = 0.01- 0.4 \text{ nC}$
- $\epsilon_n = 0.1-1 \text{ mm-mrad}$
- five SRF 2-cell cavities
- symmetric beam line
 - twin coax input couplers
 - round beam line absorbers
- beam line HOM loads for aggressive HOM damping
- cold cavity fine-alignment






Design Philosophy

- Use the same cryomodule concept in ERL injector and main linac.
- Cryomodule concept based on the well established TTF cryomodule
 - Cavities supported by large diameter Helium-gas return pipe (HGRP)
- Significant modifications for ERL specific needs:
 - high cryo loads at 1.8K (cavity), 5K and 80K (HOM power, input couplers), high Q_0 , HOM loads, ...
- Continue simplification and cost reduction




Design Modifications and Innovations

- **Changes compared to TTF cryomodule:**
 - Increase diameter of 2-phase 2K He pipe for CW cavity operation
 - **Direct gas cooling of chosen 5K and 80K intercept points with He-gas flow through small heat exchangers**
 - HOM absorbers between cavities.
 - **3 layers of magnetic shielding for high Q_0**
 - No 5K shield, only a 5K cooling manifold.
 - **Tuner stepper easily replaceable while string is in cryomodule**
 - New end-cap and feed-cap concept with reduced length
 - **In-situ bake for input couplers, no further atmosphere exposure, *no pre-conditioning***






Fixed Cavity and HOM Load Supports




- Precision fixed surfaces between the beamline components and the HGRP \Rightarrow easy “self” alignment
- Cavity-subunits can be fine-aligned while cavities are at 2K (if required)






Along the Way: The Test Cryomodule



- Vacuum vessel can be used later as an ERL main linac cavity test cryomodule
- Assembly in progress

- *Single* cavity test version of full injector module
 - Same concept,...
 - ... just shorter






The Beam Line Components: Design, Fabrication and Test



Superconducting 1.3 GHz 2-cell Cavities



- Brazed conflat flanges
- Twin-input coupler
- 6 cavities fabricated and tested in house
- Only BCP, no 800C
- All cavities meet 15 MV/m spec




Paper WEPMS007

EB Welding



Cavity Tuning



BCP





HPR





Coaxial Input Couplers


- Design for high cw power > 50 kW
- 2 prototypes tested up to 50 kW cw, 80 kW pulsed
- 10 couplers ordered with further improved cooling






Beam Line HOM Loads

| | |
|-----------------------|---------------------|
| Power per load | 26 W (200 W max) |
| HOM frequency range | 1.4 – 100 GHz |
| Operating temperature | 80 K |
| Coolant | He Gas |
| RF absorbing tiles | TT2, Co2Z, Ceralloy |




- 2 proto-types fab'ed by Cornell
- 6 production loads fab'ed by industry





Frequency Tuners

- Modification of the INFN blade tuner
- Added piezos for microphonics compensation (R&D)
- Stepper motor easily replaceable while cavity string is in cryomodule
- 6 units fabricated






Finished Beam Line for Test Module

HOM load

cavity

HOM load

gate valve





The Test Cryomodule: Assembly




Test Cryomodule Assembly

Helium-gas
return pipe;
serves also
as main
beam line
support
structure





Mounting of Beam Line to HGRP



Support
post


Helium-gas
return pipe

Precision
fixed
supports

Beam line



Beam Line supported by HGRP






120C Cavity and Coupler Bake (cold part)

In-situ bake
for cold and
warm
couplers, no
further
atmosphere
exposure, no
pre-
conditioning





Add Magnetic Shield I, Frequency Tuner





**Cavity
frequency
tuner with
magnetic
shield below
blades**




Cryomodule Instrumentation

- 90 sensors (T, He-level, ...)
- 5 heaters (2K, 5K, 80K)
- In-situ coupler bake
- 22 RF cables





Add 80K Thermal Shield






Tuner Motor Access Port in 80K Shield


Tuner
stepper
easily
replaceable
while string
is in
cryomodule

80K thermal
shield





Gate Valve inside of Module with outside Drive






Add Magnetic Shield III






Add Superinsulation






Align Cold Mass and Vacuum Vessel

Rail system
to slide
cold-mass
into
vacuum
vessel






Slide Cold-Mass into Vacuum Vessel






...keep going





Done





Insight from the Assembly


- First assembly revealed no significant design problems
- Fast, easy assembly (once we had all parts...)
- Fixed alignment concept works well
- Full 3D modeling (including assembly drawings) extremely helpful
- Tight tolerances are cost drivers \Rightarrow spec carefully!
- Several small improvements have been applied to the full injector module design to reduce cost further



Getting Ready for Test



- 135 kW cw power klystron (e2v)
- Cold-box with 2K, 5K, 80K heat exchanger
- 50 W @ 1.8K pumping skid/refrigerator




June 28, 2007

12/20/2006 09:48



What's next?

- Test-cryomodule test 7/07
- Full injector cryomodule assembly 8/07 – 1/08 (all cryo-vessel parts have been ordered)
- Beam test in 2008





Cornell ERL SRF Team

H. Padamsee

M. Liepe

S. Belomestnykh

E. Chojnacki

J. Sears

V. Medjidzade

D. Meidlinger

V. Veshcherevich

V. Shemelin

P. Quigley

D. Heath

P. Barnes

B. Clasby

J. Kaufman

A. Windsor

R. Roy

R. Ehrlich

E. Smith