



LHC Beam Instrumentation

Particle Accelerator Conference 07

Albuquerque, New Mexico, USA

25th - 29th June 2007

Rhodri Jones

(CERN Beam Instrumentation Group)




Overview

- What's Required & When
- Distributed Systems
 - Beam position measurement
 - Beam loss measurement
- Other Systems
 - Tune, chromaticity & coupling measurement
 - Collision rate measurement
 - Beam size measurement



Instrumentation - what's required & when


- First turn
 - Screens, BPMs, fast BCT, BLMs
- Circulating beams at 450 GeV
 - DC BCT & lifetime
 - Tune Coupling & Chromaticity
 - Emittance: wire scanners
- Snapback and Ramp
 - Continuous Orbit, Tune, Coupling & Chromaticity (+ feedback)
 - Continuous emittance monitoring: synchrotron light, IPM
- First Collisions
 - Luminosity
 - Schottky





Beam Position System Challenges

- Pick-up requirements
 - Mechanics that can operate at $\sim 4\text{K}$
 - Maximise aperture & signal strength
 - Minimise transverse impedance
- Dynamic Range
 - From 1 bunch of 1×10^9 charges to 2808 bunches of 1.7×10^{11} charges
- Linearity
 - Better than 1% of half radius, $\sim 130\mu\text{m}$ for arc BPMs
 - Over whole intensity range
 - Over large fraction of the aperture
- Resolution
 - In the micron range for accurate global orbit control
 - Driven by collimation requirements
 - Over 120 collimator jaws in the LHC





BPM Acquisition Electronics

Amplitude to Time Normaliser

Advantages



- Fast normalisation ($< 25\text{ns}$)
 - bunch to bunch measurement
- Signal dynamic independent of the number of bunches
 - Input dynamic range $\sim 45\text{ dB}$
 - No need for gain selection
- Reduced number of channels
 - normalisation at the front-end
- $\sim 10\text{ dB}$ compression of the position dynamic due to the recombination of signals
- Independent of external timing

Limitations


- Currently reserved for beams with empty RF buckets between bunches
 - LHC 400MHz RF but 25ns spacing
 - 1 bunch every 10 buckets filled
- Tight time adjustment required
- No Intensity information
- Propagation delay stability and switching time uncertainty are the limiting performance factors




The Wide Band Time Normaliser



The Wide Band Time Normaliser




Δt depends on position \leftrightarrow




LHC Beam Position System Layout

'LHC' BEAM POSITION MEASUREMENT






Orbit feedback results from the CERN-SPS





The LHC Beam Loss System

Coping with a Huge Stored Beam Energy



Quench Levels	Units	<i>Tevatron</i>	<i>RHIC</i>	<i>HERA</i>	<i>LHC</i>
<i>Instant loss (0.01-10 ms)</i>	[J/cm ³]	4.5 10 ⁻⁰³	1.8 10 ⁻⁰²	2.1 10 ⁻⁰³ - 6.6 10 ⁻⁰³	8.7 10 ⁻⁰⁴
<i>Steady loss (> 100 s)</i>	[W/cm ³]	7.5 10 ⁻⁰²	7.5 10 ⁻⁰²		5.3 10 ⁻⁰³




The LHC Beam Loss System

Role of the BLM system:

1. Protect the LHC from damage
2. Dump the beam to avoid magnet quenches
3. Diagnostic tool to improve the performance of the LHC

<i>Name</i>	<i>Type</i>	<i>Number</i>	<i>Area of use</i>	<i>Maskable</i>	<i>Time resolution</i>
BLMAI	Ionisation Chamber	~3000	Arcs	yes	1 turn
BLMCI BLMCS	Ionisation Chamber SEM	~150 ~150	Collimation regions	no	1 turn
BLMSI BLMSS	Ionisation Chamber SEM	~400 ~150	Critical aperture limits or positions	no	1 turn
BLMB	ACEM	~10	Primary collimators	yes	bunch-by- bunch

BLM Detection Range



- Pilot bunch of 5×10^9 close to damage level at 7 TeV
- Loss of 3×10^{-7} of nominal beam over 10ms can create a quench at 7 TeV

Beam Loss Detectors

- Design criteria: Signal speed and reliability
- Dynamic range ($> 10^9$) limited by leakage current through insulator ceramics (lower) and saturation due to space charge (upper)

Secondary Emission Monitor (SEM):


- Length 10 cm
- $P < 10^{-7}$ bar
- ~ 30000 times smaller gain

Ionization chamber:

- N_2 gas filling at 100 mbar over-pressure
- Length 50 cm
- Sensitive volume 1.5 l
- Ion collection time $85 \mu s$

Both monitors:

- Parallel electrodes (Al or Ti) separated by 0.5 cm
- Low pass filter at the HV input
- Voltage 1.5 kV




Installed BLM Monitors






BLM Threshold Level Estimation



BLM Acquisition Electronics



Implemented on VME64x Board



- **Threshold Comparator:**
 - Losses integrated and compared to threshold table
 - 12 time intervals and 32 energy ranges).




Tune, Chromaticity & Coupling

- Clear three step approach:
 - 1) Day 1 with kicked beams and classical motion analysis
 - Q kicker for both planes & both beams (limited to 2Hz rep rate)
 - Base Band Tune (BBQ) system for tune & coupling
 - Head-tail system for chromaticity
 - Chirp excitation using transverse damper allows faster repetition rate
 - 2) Day N with PLL tune tracking (US-LARP)
 - Continuous tune and coupling measurements
 - $\delta p/p$ modulation via RF allows continuous chromaticity measurement
 - 3) Day N++ with PLL measurement & Feedback (US-LARP)
 - Fully automatic tune, chromaticity & coupling control
- For operational beams the additional problems will be:
 - lowering the excitation level to an insignificant level
 - coping with coupling
 - achieving compatibility with resistive transverse damping




Measuring with Little or No Excitation – The Base Band Q Measurement (BBQ) System







Setting-up the 25ns LHC Beam in the SPS





PLL tracking in the SPS

Resonantly Extracted 25ns LHC Beam in the SPS Real-time Tune Display



- Nominal Beam - PLL OFF
 - tune hardly visible


- Nominal Beam – PLL ON
 - tracking achieved throughout cycle




Coupling via PLL Tune Tracking

Start with decoupled machine → Only horizontal tune shows up in horizontal FFT

Gradually increase coupling → Vertical mode shows up & frequencies shift





FFT of Horizontal Acquisition Plane






Tune & Coupling Feedback at RHIC (2006)




Collision Rate Monitoring


- Requires a region where signal is proportional to collision rate
 - Can be found in the neutral absorber (TAN) at ~150m from the IP
 - Ionisation chambers supplied by LBNL (Berkeley) as part of US-LARP
- The Challenges
 - Has to withstand a very harsh radiation environment
 - Has to provide 40MHz bunch by bunch data with 1% relative accuracy



TAN Collision Rate Monitor





TAN Collision Rate Monitor





TAN Collision Rate Monitor

Recent Results from Tests at RHIC






Measuring Beam Size

- Beam Profile Measurements in the LHC
 - For injection, dump & matching
 - Phosphor and OTR screens

Dump line
BTV tanks
awaiting final
installation





Measuring Beam Size

- Beam Profile Measurements in the LHC
 - Workhorses
 - Wire scanners for cross calibration ($30\mu\text{m}$ carbon wire at 2ms^{-1})

Wire scanner tanks
and mechanisms
in place





Measuring Beam Size

- Beam Profile Measurements in the LHC
 - Workhorses
 - Wire scanners for cross calibration ($30\mu\text{m}$ carbon wire at 2ms^{-1})
 - Synchrotron light monitor
 - For ions
 - Rest Gas Ionisation Monitor
 - Also used as back-up for SR monitor


Rest gas
ionisation
chambers and
compensation
magnets in place





Abort Gap Monitor

- Avoid quenches during a programmed beam dump or at start of ramp
- System based on gated photomultiplier
- Tested in SPS on 450GeV fixed target beam with synchrotron light source
 - Observation of injection kicker gap while beam is debunched



LHC Quench level at 7TeV is 7×10^7 protons per 100ns

- 0.2ppm of nominal beam
- Detection required at 1/10th of quench level
 - 18,000 photons/100ns/turn

Available light

- Light is shared with the synchrotron light monitor
- Fast, gated photomultiplier has efficiency of $\sim 7\%$

Requires detection of 128 photons/100ns/turn



Summary

- Installation of the vacuum components for LHC beam instrumentation is nearing completion
 - Acquisition systems for BPM & BLM systems are being hardware commissioned
 - Production of acquisition systems for other monitors will shortly be complete
- Significant progress has been made to address the remaining challenges
 - Much of this has been made possible through collaboration and testing on existing machines such as HERA, RHIC and Tevatron.
- LHC will turn on with a comprehensive set of beam instrumentation

Acknowledgements

Many thanks to all the members of the Beam Instrumentation Group at CERN & our European and US collaborators for their input for this presentation.