

ILC Main Linac Issues and Evolving SRF Test Facilities

Bob Kephart

Fermilab

for the Global Design Effort



International Linear Collider


New energy frontier machine proposed for HEP

Parameters

- Electron-Positron Collider
- E_{cm} adjustable from 200 – 500 GeV
- Luminosity $\rightarrow \int L dt = 500 \text{ fb}^{-1}$ in 4 years
- Energy stability and precision below 0.1%
- Electron polarization of at least 80%
- The machine must be upgradeable to 1 TeV

Overview

- The ILC is based upon a Superconducting Radio Frequency (SRF) linacs of unprecedented scope (length=23 km, 1680 Cryomodules, 14,560 SRF cavities, 31.5 MV/m)





ILC ML Beam Parameters


Parameter	Value	Parameter	Value
Initial Beam energy	15 GeV	Initial $\gamma\varepsilon_x$	8.4 μm
Final Beam energy	250 GeV	Final $\gamma\varepsilon_x$	9.4 μm
Particles per Bunch	2×10^{10}	Initial $\gamma\varepsilon_y$	24 nm
Beam Current	9.0 mA	Final $\gamma\varepsilon_y$	34 nm
Bunch Spacing	369 ns	σ_z	0.3 mm
Bunch train length	969 μs	Initial σ_E/E	1.5%
Number of bunches	2625	Final σ_E/E	0.1%
Pulse repetition rate	5 Hz	Beam phase wrt RF crest	5°

Average beam power is 11 MW / beam \rightarrow wall plug to beam efficiency is crucial \rightarrow Superconducting RF



ML basic building block

ILC RF Unit: 3 CM, klystron, modulator, LLRF



Baseline design now has 2 CM with 9 cavities, 1 CM with 8 cavities + quad




Issues for ILC linac

- Key issues for ILC Physics
 - Machine Energy, Luminosity, Availability
- Technical Challenges
 - Achieving high gradient in SRF cavities with a reproducible process
 - Building cryomodules with these cavities that meet ILC specification
 - Developing a reliable and efficient RF power source
 - Industrialization of high volume components
 - Cost !
- The Global Design Effort is addressing these challenges via a worldwide R&D program with specific goals
- **Key to achieving these goals are evolving ILC Development and Test Facilities**, the subject of this talk



Cavity/CM process and Testing



Plan... Develop in labs then transfer technology to industry



SCRF Infrastructure

- This process requires extensive infrastructure
- Bare cavities
 - Fabrication facilities (Electron beam welder, QC, etc)
 - Surface treatment facilities BCP & Electro-polish facilities (EP)
 - Ultra clean H₂O & High Pressure Rinse systems
 - Vertical Test facilities (Cryogenics + low power RF)
- Cavity Dressing Facilities (cryostat, tuner, coupler)
 - Class 10/100 clean room
 - Horizontal Test System (cryogenics and pulsed RF power)
- String Assembly Facilities
 - Large class 10/100 clean rooms, Large fixtures
- Cryo-module test facilities
 - Cryogenics, pulsed RF power, LLRF, controls, shielding, etc.
 - Beam tests → electron source (RF unit test facilities)



Cavity and Cryomodule Goals

- The GDE has established project wide R&D goals for ILC cavities and cryomodules (labeled as S0,S1,S2)
- **S0 goal:** Establish a process & controls to reliably achieve 35 MV/M in bare cavity tests (80% yield)
- **S1 goal:** Complete an ILC Cryomodule with all cavities at working at accelerating gradients >31.5 MV/M (Average)
- **S2 goal:** Demonstrate a fully qualified ILC RF unit
- **Achieving these goals requires extensive SRF infrastructure & a coordinated International R&D program**



Goals of ILC RF Unit Tests

From S2 task force report

- Demonstrate an RF unit operating at ILC specifications
- Understand RF control issues
 - RF phase and beam energy control
 - Cavity gradient spread that can be handled by LLRF
 - RF fault recognition and recovery software
- Demonstrate beam based feedback schemes
 - steering, energy, and intra-train feedback
- Measure
 - CM static and dynamic heat loads ,cavity dark current, etc
- Determine component MTBF and other CM weaknesses before large scale industrial production
- Test transport & interoperability of CM from different regions

ILC RF unit test facilities will address these issues



Regional ILC R&D efforts




- 3 Regions currently involved
 - **Europe:** Primarily DESY but also Italy, France, U.K., and growing efforts in Russia and at CERN
 - **Asia:** Primarily KEK, but growing efforts in India, Korea, China
 - **Americas:** FNAL, SLAC, TJNL, Cornell, ANL, LBNL, LLNL, LANL, MSU, Triumpf, etc
- Can't cover it all... focus on Main Linac beam test facilities (DESY, KEK, FNAL)

The TESLA collaboration centered at DESY developed the SRF technology adopted for ILC. DESY is the world leader

- Cavity R&D
 - 9 cell TESLA shape (baseline for ILC)
 - Electropolishing development
 - Large grain Nb, hydroformed
- Cryomodule and RF power Development
- TTFII/Flash ~ RF unit test facility for XFEL
- Industrialization of SRF technology



- TTFII/FLASH
 - TTFII: was originally a test facility for TESLA (ILC)
 - TTFII SRF linac now drives VUV-FEL (FLASH) providing light for BES users
 - Machine time still available as ILC test facility
- XFEL (European Project)
 - Recently approved for construction at DESY
 - 20 GeV SRF linac driven light source
- DESY Facilities (ramping up in support of XFEL)
 - Cavity fabrication, processing, test facility upgrades
 - Cryomodule fabrication → industrial training for XFEL

FLASH Overview






250 m

FLASH Overview





250 m

FLASH Overview





250 m

FLASH Overview





250 m

FLASH Overview




← 250 m →

FLASH uses TESLA CM's




FLASH uses TESLA CM's



FLASH uses TESLA CM's




Performance of Recent CM #7



- Recent CM experience

- CM 6 had 5 cavities over 30 MV/M (but 2 went down WRT HTS)
- CM 7 had 6 of 8 cavities above 30 MV/M (encouraging)

- ILC related performance:
 - Operations: 13% unscheduled down time (mostly RF sys)
 - Phase stability: 0.14° of 1.3 GHz or 300 fs
 - $dE/E = 2.4 \cdot 10^{-4}$ measured at 127 MeV
- Plans:
 - Add 6th CM, beam energy \rightarrow 1 GeV/c
 - Improve electron gun (reduce dark current)
 - Add 3rd harmonic CM (FNAL), doubles FEL light output
- FLASH operations, ILC studies, Construct XFEL !!!
 - ~30% of time is available for Accel dev and ILC R&D



STF (Asia)

- Superconducting Test Facility (STF)
 - Location: KEK, Japan
 - Purpose: General SRF test facility in support of the ILC
 - Status: Under construction
- Facilities
 - Cavity fabrication, processing, test
 - ILC module fabrication
 - ILC module test facility
 - Plan: Evolve into RF unit test facility


STF Facility KEK

Refrigerator

Cryogenic System
(from AR-East)



Control Room



Klystron Gallery

Clean Rooms



Cryomodule Assembly



EP Facility



HPR

STF R&D Activities (Asia)

- Cavity R&D
 - 9 cell TESLA shape (baseline for ILC)
 - 9 cell Ichiro cavities (goal = higher E_{acc})
 - Seamless cavities (hydroformed)
 - Single cell EP R&D
- Cryomodule & RF Power development
- ILC RF unit test facility
- Industrialization of SRF technology


Cavity R&D at KEK

- **4 Tesla Shape cavities**
- Processed and vertical tested
- 3 cavities achieved ~ 20 MV/m
- 1 achieved 30 MV/m, installed in CM
- Performance limited by field emission




- **4 Ichiro cavities**

- Reentrant design lowers B at fixed Eacc
- Single cells: 6 examples **all > 40 MV/M**
- But... so far 9 cells are only 12-20 MV/M
- Limited by multipacting in end groups
- End groups removed \rightarrow 1 achieved 29 MV/M
- One 19 MV/m Ichiro cavity installed in CM



Ave. Eacc = 46.7 ± 1.9 MV/m


Scattering 5%



STF Plan

- **Phase 1 (2005-07) Develop SRF cavities & infrastructure**
 - Two types of cavities: TESLA and Ichiro (35 → 45 MV/m)
 - Start with two 4 M cryostats (access to STF tunnel)
 - 1 cavity in each short cryostat Now !
 - 4 cavities in each short cryostat Sep 2007
 - Improved cavities Apr 2008
- **Phase 2 (2008 – 10) Develop ILC Main Linac RF unit**
 - Built Cryomodule test facility
 - CM Fabrication 2009-10
 - Build RF power test infrastructure now-2010
 - RF unit test 2011
- **In parallel with phase 1,2**
 - GDE S0 task force (demonstrate 35 MV/M gradient)
 - Industrialization

Plan of STF Phase 2 beam line



- **Phase 2 Beam (2011)**

- 2 SC beam capture cavities
- RF gun, (collab with FNAL)
- Bunch charge, structure, and current similar to ILC



Existing Short Cryomodules


R&D Activities (Americas)

- Cavity R&D
 - 9 cell TESLA shape (baseline for ILC)
 - Large grain Nb (TJNL, FNAL)
 - Electropolishing (Cornell, TJNL, ANL/FNAL)
- Cryomodule design & fabrication (FNAL)
- RF power development (SLAC)
- ILC RF unit test facility (FNAL)
- Industrialization just starting

U.S. Cavity R&D = National effort



JLab

Electropolish



**Several cavities
> 30 MV/m in vertical test**

Cornell



Vertical EP

ANL/FNAL Collaboration



**ANL: New clean rooms,
state-of-the-art EP**



**FNAL: New Vertical
Test Facility**



Horizontal Test System (FNAL)

- After vertical test extensive cavity handling ensues
 - Cavity welded inside He vessel
 - Cavity opened to install main coupler
 - Tuner added
- Horizontal Test
 - First test of the cavity with high pulsed RF power
 - R&D Test bed: tuners (slow), couplers, LLRF, etc.
- NEW HTS facility is nearly complete at FNAL

} **“Dressing”**

**1.3 GHz
Cavity in HTS
Cryostat**



**HTS
Cryostat**




RF Power for HTS



- ILC RF unit test facility
- Location: Fermilab “New Muon Building” (NML)
- Goal: Address the GDE “S2 Goals”
 - Demonstrate a complete ILC RF unit with ILC-like beam
 - Also crab-cavity R&D, diagnostics development, personnel training, and advanced accelerator R&D.
- ILC-like beam
 - 3.2 nC/bunch @3 MHz
 - Up to 3000 bunches @ 5Hz
 - Bunch length: 300- μ m rms
 - Injector Energy: 30-40 MeV (to avoid over focusing in ILC CM)
 - To understand CM need “known” beam parameters @ CM entrance and exit → good diagnostics

ILCTA_NM (FNAL)



A0 Photo Injector

- The A0 Photo Injector built in collaboration with DESY as part of the TESLA collaboration (essentially a copy of TTFI)
- In operation since late 90's
- Two klystron-based RF systems power the RF Gun & Capture Cavity
- Built a second capture cavity (CCII) using high gradient DESY cavity
- A0 RF assets and CCII will be moved to NML in 2008



RF Gun prior to solenoid installation



Capture Cavity and beamline



Capture Cavity-II

ILCTA Plans

- Effort is Funding limited → phased approach
- Cryomodule delivery
 - 1st (Type 3+) cryomodule built from “kit” of DESY parts in late 2007
 - 2nd (Type 3+) CM – 2008 built with U.S. processed cavities
 - 3rd (ILC Type 4) CM – 2009 all U.S. components
 - Replace all three CMs with ILC Type 4+ in FY2010
- FY07: Start as a Cryomodule Test Stand
- FY08: move A0 photoinjector, start civil construction for new bldg
- FY09: 1st beam operation, 2-3 CM, low rep rate operations
- FY10: replace all 3 CM with ILC type CM
- FY11: install new refrigerator, ILC RF Unit operations
- Collaboration: DESY, INFN, ANL, Cockroft, NIU, Rochester, KEK



NML Building



NML: June 07

Cavities for 1st CM @ FNAL



1st of 2 refrigerators each 60 W@1.8K



Parts for 1st CM at DESY



FNAL Clean Room & CM assembly Area

Summary

- **The International Linear Collider will employ an SRF linac of unprecedented scope**
- **Cavities & Cryomodules are cost drivers for ILC**
- **There are many issues to be addressed to demonstrate the required performance for ILC**
- **All three regions have mounted large R&D programs to explore these issues (I apologize for omissions)**
- **Extensive infrastructure is needed to support this R&D and ILC industrialization**
- **Large scale RF unit test facilities are a key**
- **Lots of progress & ambitious plans**